



## CONSTRUCTION CODES UPDATE PAGES

Attached are Construction Codes Update Pages. These pages reflect local laws enacted and ministerial administrative corrections made after July 1, 2008. Please note that the source of a particular update, the local law number, and year is indicated on each page. Please visit our [webpage](#) to ensure that your codes are complete and up to date as the City Council may periodically pass Local Laws that affect the Construction Codes.

### **Instructions:**

Please place each page, according to its page number found on the bottom right hand corner, into your Construction Codes books. The pages contain letters after the page number and should be placed in alphabetical order following the number, i.e. 5, 6, 6a, 6b, etc.

- Place Title Pages in the front of your Code books for easy reference.
- Note: If you have all four Construction Codes (Building, Mechanical, Plumbing & Fuel Gas), please make sure to insert updates made to the Administrative Provisions into each of the four Code books.

# CONSTRUCTION CODES UPDATE PAGES

## UPDATE # 28

Source: Local Law 64 of 2009, effective February 4, 2010.

This update includes the following pages:

<b>BUILDING CODE</b>	
<b><u>Section</u></b>	<b><u>Page Number</u></b>
3303.8.1	602c-f

## CONSTRUCTION CODES UPDATE PAGE

Matter in plain text is unchanged. Matter underlined is new. Matter ~~stricken through~~ is deleted.

Source: Local Law 64 of 2009, effective February 4, 2010.

## BUILDING CODE

*Insert between pages 602b and 603 of your bound volume.*

Add the following new section 3303.8.1:

**3303.8.1 Air pressurized alarm system for dry standpipe systems during construction or demolition operations.** Air pressurized alarm systems shall be provided as set forth in Items 1 through 5 below. The provisions of NFPA 14, Chapter 12, as modified in Appendix Q, shall also apply.

1. Demolitions. In vacant buildings and structures undergoing demolition, all existing standpipes shall be maintained in a state of readiness as dry standpipes in accordance with Item 2 of Section 3303.8 and shall be provided with an air pressurized system.
2. New buildings and structures. All required permanent or temporary standpipes shall be in a state of readiness once the work reaches a height greater than 75 feet (22 860 mm) and shall contain an air pressurized alarm system.
3. Submission of application. An application to install an air pressurized alarm system shall be filed by a registered design professional and a permit obtained by a licensed master plumber or licensed master fire suppression piping contractor. A licensed electrician shall obtain all required electrical permits in accordance with Chapter 3 of Title 27 of the *Administrative Code*.
4. Specifications. The following provisions shall apply to the air pressurized alarm system:
  - 4.1. Pressure. Pressure shall be maintained in the standpipe and cross connections at all times and shall not exceed 25 psig (172 kPag) by utilizing nitrogen or an air compressor with an air dryer. The supervisory pressure shall be as determined by a registered design professional.
  - 4.2. Automatic air pressurized alarm activation. The alarm shall be automatically activated when the pressure drops below the supervisory pressure or rises above the maximum pressure of 25 psig (172 kPag). When the alarm is activated, notification shall be made to the Fire Department in accordance with Section 901.7.7 of the *New York City Fire Code*, all work at the site shall cease, except as provided in Item 4.2.1, and an investigation of the entire standpipe system and air compressor shall be immediately performed

## CONSTRUCTION CODES UPDATE PAGE

Matter in plain text is unchanged. Matter underlined is new. Matter ~~stricken through~~ is deleted.

**Source:** Local Law 64 of 2009, effective February 4, 2010.

to determine the cause of the alarm. Unless authorized by the Fire Department, no construction or demolition work shall resume until the standpipe system is repaired and the appropriate pressure is restored, except that any repairs to the standpipe system needed to restore the required pressure shall be undertaken immediately and the standpipe system restored as soon as possible. There shall be compliance with the requirements of Section 901.7.7 of the *New York City Fire Code* while the standpipe system is out of service. Upon completion of repairs to the standpipe system a full inspection of such system shall be performed, which shall include, among other things, visually tracing the standpipe, including risers, cross connections and siamese connections to verify that no breach exists and checking all gauges of the standpipe system to ensure the standpipe system has been restored to a state of readiness.

4.2.1. Notwithstanding the provisions of Item 4.2, the activation of the alarm shall not require the cessation of work necessary for the completion of concrete pouring operations in progress at the time of alarm activation, where such cessation would cause a cold joint that would impair the structural integrity of the finished construction. The continuation of such operations shall be permitted only until an orderly termination of such operations can be effectuated. The site safety manager or coordinator shall record the names and locations of any employees necessary for the completion of the concrete pouring operations and provide them to the Fire Department personnel who arrive on the scene.

4.3. Air compressor. The air compressor shall be designed to automatically cut in and cut out at the supervisory pressure and shall be tied into the standpipe system between the siamese connections and the house check valves. The air compressor shall utilize an air dryer during times when freezing conditions exist to condition the air entering the dry standpipe system.

4.4. Alarm. The standpipe alarm system shall utilize pressure switches and control equipment to annunciate a local audible alarm on site that can be heard during working and non-working hours. The audible signal of the horn shall be at least 15 dBA above the ambient noise level but no more than 110 dBA.

4.5. Power supply. The standpipe alarm system shall be connected to an active, dedicated power supply at all times.

## CONSTRUCTION CODES UPDATE PAGE

Matter in plain text is unchanged. Matter underlined is new. Matter ~~stricken through~~ is deleted.

**Source:** Local Law 64 of 2009, effective February 4, 2010.

- 4.6. Check valves. Check valves shall be installed to prevent water from entering the air compressor.
- 4.7. Locks and caps. All control valves shall be chained and locked in the appropriate position and shall be provided with capped outlets. All hose valves shall also be provided with capped outlets.
- 4.8. Fire Department connections. Three inch (76 mm) iron hose plugs with gaskets in Fire Department connection swivels shall be provided.
- 4.9. Drainage. Provisions shall be made to drain water in any trapped sections of the dry standpipe system that are subject to freezing.
- 4.10. Manual air release connection. A minimum 2.5-inch (64 mm) connection located immediately downstream of the Fire Department siamese connection check valve shall be provided and piped to a location immediately adjacent to the siamese connections. This line shall be fitted with a 2.5-inch (64 mm) hose valve and shall allow for release of the pressurized air from the dry standpipe system. The number of air release valves provided shall be such that the air pressure shall be released in no more than 3 minutes, which shall be verifiable by an actual air release test performed at the time of the initial installation.
- 4.11. Construction documents. Plans shall identify all standpipe risers, cross connections, siamese connections, any intermediate check valves that have to be removed, proposed location of the air release connections, designation of the supervisory pressure, complete information regarding the alarm system, and procedures for the safe pressurization and depressurization of the system.
- 4.12. Signage. Signage shall be provided at all siamese connections indicating that the dry standpipe system is pressurized and showing the location of the manual air release.
5. Planned removal from service of standpipe system and standpipe air pressurized alarm. Whenever the standpipe system is to be placed out of service for the addition of a new section to the system, removal of an existing section as demolition operations progress, or other planned event, the standpipe alarm may be temporarily deactivated subject to compliance with the requirements of Section 901.7.7 of the *New York City Fire Code*. Where a site safety manager or coordinator is required by Section 3310.5 of this code, all alarm activations,

## CONSTRUCTION CODES UPDATE PAGE

Matter in plain text is unchanged. Matter underlined is new. Matter ~~stricken through~~ is deleted.

**Source:** Local Law 64 of 2009, effective February 4, 2010.

inspections, and repairs shall be logged into the log book maintained by such site safety manager or coordinator. If the standpipe system is not returned to a state of readiness and the alarm reactivated within 2 hours of such planned removal from service, all construction or demolition work at the site shall cease, unless otherwise approved by the Fire Department.