



# **NYC Department of Environmental Protection**

---

## **Green Infrastructure Program**

June 10, 2013



## ❖ **Green Infrastructure Program**

- Stormwater in NYC
- Green Infrastructure Approach
- Program Implementation

## ❖ **2012 Stormwater Pilot Monitoring Report**


## ❖ **Questions and Answers**

- ❖ Approximately 60% of the City's sewers are combined sewers – meaning that the system handles sanitary waste from homes and businesses and stormwater runoff from streets, sidewalks
  
- ❖ 7,400 miles of sewers
  - 3,337 miles of combined
  - 2,271 miles of sanitary
  - 1,801 miles of storm
  - 400 acres of Bluebelts




# Impervious Surfaces & Dense Landscapes

Impervious surfaces cover 72%  
of NYC's land area




# Wet Weather May Result in CSOs

Dry Weather Conditions



Wet Weather Conditions



# Water Quality in New York City Harbor



 = does not meet water quality standards

**75%** of Harbor meets pathogen standards for swimming

**19%** meets standards for boating, fishing

**7%** of our Harbor is made up of tributaries that do not meet secondary contact standards



## NYC GREEN INFRASTRUCTURE PLAN

A SUSTAINABLE STRATEGY FOR CLEAN WATERWAYS

Michael R. Bloomberg, Mayor  
Cos Holloway, Commissioner



## 2010 – NYC Green Infrastructure Plan

Laid framework to use green infrastructure to manage stormwater runoff from 10% of impervious surfaces in combined sewer areas by 2030.

STATE OF NEW YORK  
DEPARTMENT OF ENVIRONMENTAL CONSERVATION

In the Matter of the Violations of Article 17 of the Environmental Conservation Law and Part 750, *et seq.*, of Title 6 of the Official Compilation of Codes, Rules and Regulations of the State of New York:

-by-

The City of New York and  
The New York City Department of Environmental Protection,

Respondents.

ORDER ON  
CONSENT  
(CSO Order  
Modification to  
CO2-20000107-8)

DEC Case No.  
CO2-20110512-25

WHEREAS:

1. The Department of Environmental Conservation ("the Department") is an executive agency of the State of New York with jurisdiction to enforce the environmental laws of the State, pursuant to the Environmental Conservation Law ("ECL"), Title 6 of the Official Compilation of Codes, Rules and Regulations of the State of New York ("6 NYCRR"), and Orders issued thereunder.
2. The Department has jurisdiction over the abatement and prevention of pollution to the waters of the State pursuant to Article 17 of the ECL and 6 NYCRR Part 750, *et seq.* This jurisdiction also authorizes the Department, as a State agency with an approved program per Sections 318, 402 and 405 of the federal Clean Water Act ("CWA"), 33 U.S.C. Section 1251, *et seq.*, to regulate the discharge of pollutants from point sources into waters of the State in conformity with the CWA.
3. Pursuant to its authority to protect the waters of the State, the Department administers the State Pollutant Discharge Elimination System ("SPDES") permit program, ECL §17-0801, *et seq.* In general, the SPDES program prohibits any discharge of pollutants to the waters of the State without a permit establishing pollutant limitations and treatment requirements. Thus, SPDES permits set certain effluent limitation parameters, determined according to ECL §17-0809 and 6 NYCRR Part 750.1.11, in order to avoid contravention of mandated water pollution control requirements and water quality standards ("WQS"). Those conditions address not only the allowable range of parameters for discharge of pollutants to waters of the State, but also the manner in which the permittee is to operate, maintain, monitor and report on its regulated facilities and activities.
4. Combined sewer overflows ("CSOs") are discharges of untreated domestic sewage from combined sewer systems, and industrial wastewaters, combined with stormwater. CSOs occur when wet weather flows are in excess of the capacity of combined sewer systems and/or the Water Pollution Control Plants they serve. CSO discharges can contribute to violations of state

## 2012 – Amended Consent Order


DEP and NYS DEC signed an historic agreement to incorporate a green and grey adaptive management approach into the CSO program.

# Green Infrastructure in New York City



# GI Application Rates and Milestone Schedule

- ❖ 1.5 billion in capital funding through 2030.
- ❖ \$192 million committed to be spent by December 2015.



- ❖ More cost effective than building large detention facilities
- ❖ Improved water quality and restored ecosystems
- ❖ Reduces urban heat island effect and provides air quality improvements
- ❖ May reduce street flooding in some rain events
- ❖ Greener neighborhoods





**Before**



**After**

# Waterbody Prioritization






**Overview:** \$192 million has been committed for green infrastructure in combined sewer areas through 2015, including Environmental Benefit Program funds.

- ❖ **Area-Wide Contracts**
- ❖ **On-site Retrofits**
- ❖ **Neighborhood Demonstration Areas**
- ❖ **Green Infrastructure Grant Program**
- ❖ **Other programmatic areas include:**
  - DPR Maintenance Program
  - Asset Management System
  - Outreach and Engagement Program




# 2013-2015 Area-wide Contracts



# Right of Way Bioswale




# ROWB Site Selection Example: Flushing Bay



- 1. Potential –**
  - Desktop Analysis
- 2. Preliminary –**
  - Walkthrough
  - Geotechnical Investigation
  - Survey
- 3. Final –**
  - Approved sites included in contract plans

-  Eliminated Potential Sites
-  Pending DOT Approval
-  Final
-  Proposed SW Greenstreet

# ROW Bioswale Construction



# Completed ROW Bioswale





# Stormwater Greenstreets



# ROWB Statistics & Costs

ROWB Types	Calculated CF Capacity	Calculated SF Managed
Type I	300	3,600
Type II	225	2,700
Type III	150	1,800
Type I - Enhanced	400	4,800
Type II – Enhanced	300	3,600




Photo: Example Type III Bioswale

## Average Costs for a Typical ROWB

Design	\$4,000
Surveys and Geotechnical	\$5,000
Construction	\$25,000
Construction Management (10% of Construction Costs)	\$2,500
<b>Total</b>	<b>\$36,500</b>

# 2012-2017 ROW Bioswale Construction Targets



## Total Impervious Surface Managed: 370,826 SF

### ❖ Public Housing - NYCHA

- Edenwald Houses, Bronx
- Seth Low Houses, Brooklyn
- Hope Gardens, Brooklyn

### ❖ Schools – SCA/DOE/TPL

- JHS 218, Brooklyn
- JHS 162, Brooklyn
- PS 261, Brooklyn
- PS 65, Brooklyn
- PS 157, Queens
- PS 194, Bronx



Trust for Public Land Schoolyard Design

### ❖ Hospitals - NYC HHC

- East New York Diagnostic Center, Brooklyn

### ❖ Parking Lots - Cultural Affairs

- Flushing Town Hall Parking Lot, Queens

# Example: Edenwald Houses, Bronx

**Project Cost:** \$7.5 m

**Construction:**  
Begins Winter 2013

## GI Technology

 Rooftop  
Collection

 Rain  
Garden

 Porous  
Paving




# Neighborhood Demonstration Areas

Current Phase to Meet 2015 Milestone


 Priority CSO Tributary Areas




Complete: April 2013



Complete: April 2013



Complete: December 2012




# Green Infrastructure Grant Program

- ❖ Three grant cycles to date
  
- ❖ \$11.1 million has been committed to private property owners
  
- ❖ Winning Projects include:
  - Green Roofs
  - Rain Gardens
  - Rooftop Farms
  - Permeable Pavers
  - Smart detention systems




**Brooklyn Navy Yard – Rooftop Farm Summer 2012**



**Queens College- Pavers/Rain Garden Fall 2012**

# Built and Designed Projects, 2011-2012





## ROW Maintenance:

- ❖ Through FY2015 (June 2015), DEP will fund Parks' department crews to maintain all green infrastructure in the right of way.
- ❖ Maintenance MOU clearly defines roles and responsibilities for ROW installations for DEP/DOT/DPR.

## Onsite Maintenance:

- ❖ Project specific maintenance agreements are developed with each partnering agency.

## ❖ Project Tracking & Asset Management System

- DEP and DOITT developing GIS-based application
- Track design & construction data of each GI asset
- Manage built assets citywide for effective maintenance and performance

## ❖ Interim Tracking System

- DEP developed a database for interim use
- System is used by partnering agencies and consultants
- Migration to final PT/AM system anticipated in 2014

Project Information						
Project Description	GI Type	GI ID	Managing / Partnering Entity	Borough	CSO Tributary	Waterbody
East New York diagnostic and treatment center	Green Roof	3037380015-A	Other (See Notes)	Brooklyn	26W-003	Jamaica Bay
JHS 218K Playground Improvements	Dual System (See Notes)	3042780001-A	TPL/SCA	Brooklyn	26W-005	Jamaica Bay
JHS 218K Playground Improvements	Dual System (See Notes)	3042780001-B	TPL/SCA	Brooklyn	26W-005	Jamaica Bay
PS 65K Playground Improvements	Dual System (See Notes)	3041020019-A	TPL/SCA	Brooklyn	26W-005	Jamaica Bay
PS 65K Playground Improvements	Dual System (See Notes)	3041020019-B	TPL/SCA	Brooklyn	26W-005	Jamaica Bay
PS 261K Playground Improvements	Dual System (See Notes)	3001880014-A	TPL/SCA	Brooklyn	RH-034	Gowanus Canal
PS 261K Playground Improvements	Dual System (See Notes)	3001880014-B	TPL/SCA	Brooklyn	RH-034	Gowanus Canal
Hope Gardens Houses (need official contract)	Rain Garden	3033150001-A	OGI	Brooklyn	NCB-015	Jamaica Bay

- ❖ Continue to analyze data on stormwater quantity control aimed at reducing CSOs
- ❖ Assess water quality benefits and reductions in pollutant loads
- ❖ Gather data on sustainability co-benefits such as pollinator use and temperature effects within localized areas of the city
- ❖ Evaluate engineering soil mixes, green roof media types, vegetation selection, and other GI components to guide development of more efficient, better performing GI for NYC
- ❖ Continue to improve standard designs and review emerging technologies and installation methods
- ❖ Continue to review existing and improve upon modeling of GI performance at various spatial scales (e.g. neighborhood, subwatershed, and watershed)

## ❖ Green Infrastructure Stakeholders

- Citizen's Group:  
*citywide public meeting and listserv*
- Steering Committee:  
*focused on GI implementation related to Green Jobs, Technical Advice & Research, Education & Engagement*

## ❖ Construction Notification

- “Bioswales are Coming to your Neighborhood” Postcard sent to mailing addresses in project areas
- Presentations to Community Boards, Elected Officials, and Local Community Groups
- Engineers provide handouts when approached by residents and businesses

## ❖ Education and Engagement

- ROW Bioswale Care Stewardship Program with MillionTreesNYC
- Rain Barrel Giveaway Programs

**BIOSWALES**  
*are coming to your neighborhood!*

- Bioswales collect stormwater that flows along the sidewalks and streets when it rains.
- This water feeds the tree and plants instead of draining into the sewer system.
- The trees, shrubs and flowers beautify the block, improve air quality and help lower temperatures in the summer.
- Bioswales reduce pollution and create healthier and cleaner waterways.
- Green infrastructure is a more cost-effective way to manage stormwater in NYC. Bioswales and other green infrastructure projects will save New Yorkers billions of dollars over the next 20 years.

Learn more about green infrastructure and how you can care for a Bioswale at [www.nyc.gov](http://www.nyc.gov).

**NYC**  
Environmental Protection  
Michael R. Bloomberg, Mayor  
Carter H. Strickland, Jr., Commissioner



- ❖ Met all 2012 green infrastructure milestones of the Modified Consent Order
- ❖ Promulgated Stormwater Performance Standards
- ❖ Published *Guidelines for the Design and Construction of Stormwater Management Systems*
- ❖ Conducted Green Infrastructure Program Environmental Review
- ❖ Released *NYC Green Infrastructure Plan: 2011 Preliminary Pilot Monitoring Results*

## 2012 Major Accomplishments

1

### Promulgated Stormwater Performance Standard

DEP's stormwater performance standard (or "stormwater rule") took effect in July 2012. By slowing the flow of stormwater to the sewers, the stormwater rule allows the City to manage stormwater runoff from new development and redevelopment more effectively and maximize, to the greatest extent possible, the capacity of the city's combined sewer systems.

2

### Signed Additional Agreements with Partner Agencies

In January 2012, building on its agreement establishing maintenance roles with the New York City Department of Parks and Recreation (DPR) and the New York City Department of Transportation (DOT), DEP finalized an agreement with the New York City Housing Authority (NYCHA). The agreement established a working relationship between DEP and NYCHA for a five year term. The agencies will amend the agreement as new projects are accepted and completed.

3

### Continued Outreach and Notification in Green Infrastructure Project Areas

In 2012, DEP expanded its outreach and notification strategies. DEP made presentations to inform communities of new green infrastructure projects within neighborhood and area-wide project areas, and coordinated with the New York City Department of Design and Construction (DDC) on construction project newsletters. DEP mailed over 25,000 postcards notifying the public of upcoming build-out of Right-of-way Bioswales and Stormwater Greenstreets in affected areas. DEP continues to participate in conferences and webinars, and hold outreach events. DEP also continues to make presentations upon request to elected officials, community boards, schools and universities, and other civic organizations.

4

### Conducted Green Infrastructure Program Environmental Review

In March 2012, the City published an Environmental Assessment Statement for the first five years of the Green Infrastructure Program. DEP, as lead agency, concluded there would be no foreseeable adverse impacts on the environment from constructing a large scale green infrastructure program, assuming a range of technologies to be constructed in concentrated throughout combined sewer areas of the city.

5

### Published Guidelines for the Design and Construction of Stormwater Management Systems

In conjunction with the implementation of the new stormwater performance standard, DEP published a companion document, *Guidelines for the Design and Construction of Stormwater Management Systems*, to assist New York City's development community and licensed professionals in the selection, planning, design, and construction of onsite source controls that comply with the new rule.

6

### Constructed Right-of-way Bioswales

In 2011 and 2012, DEP constructed 14 Right-of-way Bioswales in conjunction with ongoing DDC capital projects on 4th Avenue and Dean Street, Atlantic Avenue in Brooklyn, and on College Point Boulevard in Queens.

7

### Initiated Public Onsite Retrofit Projects

In 2012, DEP reviewed designs for five schoolyard sites with the Trust for Public Land and the School Construction Authority (SCA). DEP and SCA are also identifying other opportunities within Priority Areas for green infrastructure retrofits. DEP and SCA identified eight schools for the next fiscal year. Additionally, DEP is currently designing green infrastructure installations for a number of NYCHA facilities, including the Seth Low Houses and the Hope Gardens Houses in Brooklyn and the Edenwald Houses in the Bronx.

## 2013 Action Plan

Building on the progress made in 2012, DEP will implement the following programs and activities in 2013, in addition to ongoing outreach and program management for Area-wide Contracts, public retrofits, the Grant Program, and the designed projects in table 6.

**1** DEP will reinstate the Rain Barrel Giveaway Program and will make educational and informational materials available on the DEP website.

**2** DEP will create standard informational placards for the green infrastructure projects built in the right-of-way to educate and engage the public as well as to provide unique identification system for each site. This will provide multiple benefits as DEP builds its O&M Program.

**3** DEP will develop a Tracking and Asset Management System to track, manage, and maintain all of the Green Infrastructure Program's decentralized system of green infrastructure assets.

**4** DEP will continue a Research and Development Program to monitor the performance of built green infrastructure projects, and employ the data to adapt existing green infrastructure designs and modeling for CSO tributary areas.

**5** BioswaleCare, a stewardship program in partnership with MillionTreesNYC, will kick-off in March 2013 with workshops beginning shortly thereafter.

**6** DEP continues to explore opportunities to partner with other City agencies related to Hurricane Sandy recovery initiatives. Currently, DEP and DOT are jointly assessing locations to build out green infrastructure in City streets affected by the storm.

**7** DEP will work with DOB, DOF and Law to modify the Rules of the City of New York to extend and enhance the Green Roof Tax Abatement.

**8** DEP will hire a Green Roof Technical Advisor to assist in the Green Roof Tax Abatement application process and educate prospective applicants.

**9** DEP will hire additional staff in 2013 to support broader implementation of the Green Infrastructure Program.

**10** DEP will continue to design and implement green infrastructure projects towards waterbody-specific application rates.

- ❖ Describes 10 specific action items for 2013
- ❖ Each action item is currently in development and/or nearing completion
- ❖ DEP will report on the progress in the 2013 Annual Report next spring

# **Stormwater Pilot Monitoring 2012 Annual Report**

- ❖ Summarize the monitoring data and observations collected in 2011 and 2012 from multiple source control projects
- ❖ Evaluate effectiveness of each source control at reducing the volume and/or rate of stormwater runoff
- ❖ Test the data collection techniques and establish a methodology for long term monitoring program
- ❖ Identify qualitative issues like maintenance requirements, appearance and community perception

## ❖ Water Quantity



- Inflow/Outflow Water Balance
- Soil Moisture at various depths- selected sites

## ❖ Weather


- Precipitation
- Evaporation/Transpiration Rates - selected sites
- Relative Humidity/Solar Radiation - selected sites

## ❖ Water/Soil Quality

# Location of Pilot Projects and Monitoring Setup



# Precipitation Patterns – Storm Depth



# Bronx River Houses: Bioretention


## Monitoring Site Area

Impervious Area 18,750 ft<sup>2</sup>


DA:GI Footprint 6:1 to 20:1




### STORMWATER CHAMBERS




### BLUE ROOF



### RAIN GARDENS



### PERFORATED PIPES



## ❖ Monitoring data from May 2011 to December 2012


Storm Characteristics		
	2011	2012
Number of Storms	45	57
Storm Depth	0.1" to 4.9"	0.1" to 2.7"
Peak Intensity	0.1 to 5.4 in/hr	0.1 to 3.2 in/hr
Storm Duration	0.4 to 54 hrs	0.1 to 41 hrs

## ❖ Maintenance:

- Removal of debris and sediment
- Mowing, mulching, and weeding




- ❖ Bioretention areas retaining much of the water they receive
- ❖ 2011 and 2012 drawdown rates are similar (~6 in/hr)
- ❖ Simple curb cuts without localized depression are about 70% effective at runoff capture
- ❖ Leaf and litter pickup can be challenging in some areas
- ❖ Majority of the plant species have survival rate > 50%



# N&S Conduit Bioretention

Impervious Area	81,870 ft <sup>2</sup>
DA: GI Footprint	11:1



# N&S Bioretention: Data Summary

❖ Monitoring data from August 2011 to December 2012



Storm Characteristics		
	2011	2012
Number of Storms	20	53
Storm Depth	0.11" to 7.78"	0.12" to 2.78"
Peak Intensity	0.24 to 4.92 in/hr	0.24 to 4.2 in/hr
Storm Duration	0.2 to 53 hrs	1.5 to 77 hrs

❖ Maintenance:

- Removal of debris and sediment from curb cuts
- Weeding and mulching



- ❖ Only 4 outflow events since installation
- ❖ Typical surface drawdown duration < 8 hours
- ❖ Ponding drawdown rate increasing, and fewer ponding events occurring, likely due to root growth.
- ❖ Inlet vegetated swales effective at infiltrating offsite runoff




# Far Rockaway Porous Pavement

<b><u>Porous Asphalt</u></b>	
Impervious Area	6,380 ft <sup>2</sup>
DA:GI Footprint	1:1

<b><u>FilterPave</u></b>	
Impervious Area	4,260 ft <sup>2</sup>
DA:GI Footprint	1:1



# Far Rockaway Porous Pavement: Data

❖ Monitoring data October 2011 to December 2012

Storm Characteristics		
	2011	2012
Number of Storms	12	54
Storm Depth	0.1" to 2.06"	0.1" to 2.53"
Peak Intensity	0.24 to 0.84 in/hr	0.12 to 4.80 in/hr
Storm Duration	3.33 to 45 hrs	0.8 to 77 hrs


❖ Maintenance Activities:

- No routine maintenance performed to date
- Filterpave resurfaced within travel lane



# Far Rockaway Bioretention

Impervious Area	9,720 ft <sup>2</sup>
DA: GI Footprint	4.2:1



## Bioretention

# Far Rockaway Porous Pavement

	Total Volume Runoff Coefficient
Standard Asphalt	0.73 +/- 0.28
Porous Asphalt	0.23 +/- 0.27
Filterpave	0.00

- ❖ Filterpave is providing excellent stormwater control, preferred use within parking stalls
- ❖ Porous asphalt is providing moderate stormwater control, with no structural issues



# Street-Side Pilots



Site	Impervious	DA:GI
Autumn Ave ETP	3,948 ft <sup>2</sup>	39:1
Blake Ave ETP	2,176 ft <sup>2</sup>	22:1
Ridgewood ETP	4,420 ft <sup>2</sup>	44:1
Union St ETP	1,679 ft <sup>2</sup>	17:1
Eastern Pkwy SSIS	19,883 ft <sup>2</sup>	99:1
Howard Ave SSIS	6,630 ft <sup>2</sup>	33:1
Ridgewood SSIS	5,513 ft <sup>2</sup>	28:1
Union St SSIS	2,231 ft <sup>2</sup>	11:1



# Street-Side Pilots: Data Summary

## ❖ Monitoring data from September 2011 to December 2012


Storm Characteristics		
	2011	2012
Number of Storms	13-17	25-27
Storm Depth	0.1" to 5.2"	0.1" to 3.3"
Peak Intensity	0.1 to 5.3 in/hr	0.1 to 4.8 in/hr
Storm Duration	0.1 to 81 hrs	0.5 to 56 hrs

## ❖ Maintenance:


- Litter pickup
- Inlet clearing
- Weeding and mulching




# Street-Side Systems: Volume Retained



Watershed drainage area to  
BMP practice 99:1




Watershed drainage area to  
BMP practice 39:1



Watershed drainage area to  
BMP practice 17:1

- ❖ 1 inch storm typically captured and retained for a number of ETP and SSIS locations
- ❖ Performance reduced at sites with large tributary drainage area ratios
- ❖ Limited capture and infiltration performance observed for SSIS along steep slope
- ❖ Buildup of litter and debris a frequent issue



# PS 118 Blue and Green Roof

## Check Dam Blue Roof


Impervious Area	3,500 ft <sup>2</sup>
-----------------	-----------------------

DA: GI Footprint	1:1
------------------	-----

## Green Roof

Impervious Area	3,500 ft <sup>2</sup>
-----------------	-----------------------

DA: GI Footprint	1:1
------------------	-----





## ❖ Monitoring data from July 2011 to December 2012

Storm Characteristics		
	2011	2012
Number of Storms	22	33
Storm Depth	0.2" to 6.6"	0.1" to 2.8"
Peak Intensity	0.24 to 3.6 in/hr	0.1 to 2.9 in/hr
Storm Duration	0.5 to 60 hrs	0.5 to 54 hrs



- ❖ Green roof retained runoff more effectively than blue roof
- ❖ Both systems significantly reduce peaks, particularly for low intensity storms
- ❖ Only minor differences in performance between 2011 and 2012



- ❖ Water and soil quality sampling performed at a number of pilots – possibly due to retrofit soil disturbance during 2012 – results may not be indicative of actual performance
- ❖ Preliminary results show no consistent evidence that NYC water quality is substantially different from other areas
- ❖ The total load of pollutants being delivered to the sewer system is being reduced due to volume retention
- ❖ Analyses ongoing to better characterize inflow and outflow and compare to other national metrics



# Next Steps

- ❖ Evaluate additional large scale opportunities (e.g., North/South Conduit type installations)
- ❖ Continue to refine soil and water quality monitoring efforts at selected sites
- ❖ Initiate monitoring of right of bioswales within the neighborhood demonstration projects
- ❖ Conduct co-benefits monitoring and analysis




**NYC Green Infrastructure Plan:**  
2012 Pilot Monitoring Update



DRAFT April 2013



- ❖ Carbon sequestration
- ❖ Urban heat island mitigation
- ❖ Reduced energy demand in buildings
- ❖ Improved habitat and ecosystem services
- ❖ Improved air quality
- ❖ Beneficial pollinators (very important!!!)



# Questions?



For more information:  
[sustainability@dep.nyc.gov](mailto:sustainability@dep.nyc.gov)

[nyc.gov/dep/greeninfrastructure](https://nyc.gov/dep/greeninfrastructure)

# GI Program Spending

- ❖ To date, the GI Program has spent a total of **\$104 million** in capital dollars.
- ❖ The GI Program plans to spend an additional **\$140 million** in capital dollars by the end of FY 16.

Program Summary	FY12	FY13	FY12 & FY13 Total
Capital	\$10,099,000	\$94,003,000	\$104,102,000
Expense	\$0	\$595,885	\$595,885
<b>TOTAL</b>	<b>\$10,099,000</b>	<b>\$94,598,885</b>	<b>\$104,697,885</b>

Capital Summary	FY12	FY13	FY12 & FY13 Total
Design	\$2,647,000	\$49,269,000	\$51,916,000
Construction/CM	\$7,452,000	\$44,734,000	\$52,186,000
<b>Total</b>	<b>\$10,099,000</b>	<b>\$94,003,000</b>	<b>\$104,102,000</b>

Expense Summary	FY12	FY13	FY12 & FY13 Total
DPR Green Infrastructure Maintenance Program	\$0	\$462,385	\$462,385
Rain Barrel Giveaway Program	\$0	\$133,500	\$133,500
<b>Total</b>	<b>\$0</b>	<b>\$595,885</b>	<b>\$595,885</b>

# LTCP Schedule

LTCP	2012				2013				2014				2015				2016				2017				2018				
	Q1	Q2	Q3	Q4																									
Alley Creek				■		★	■																						
Coney Island							■	■		★	■																		
Hutchinson River								■	■		★	■																	
Flushing Creek								■	■		■	★	■																
Gowanus Canal							■	■	■	■	■	■		★	■														
Bronx River										■	■	■		★	■														
Jamaica Bay & Tributaries															■	■		★	■										
Westchester Creek															■	■		★	■										
Flushing Bay																			■	■		★	■						
Newtown Creek															■	■	■	■	■	■		★	■						
Citywide																	■	■	■	■	■	■	■	■		★	■		

■ LTCP Development and Public Participation Schedule

★ LTCP Submittal to DEC

## TreeLC and BioswaleCare Workshop



Join **MillionTreesNYC** and the **NYC Department of Environmental Protection** in partnership with the **New York City Housing Authority** for a free joint TreeLC and BioswaleCare workshop. Come learn how you can care for street trees and the new bioswales in your neighborhood!

### UPCOMING WORKSHOPS

Wednesday, June 19th at Hope Gardens  
422 Central Avenue, Brooklyn NY 11221  
6:30pm to 8:30pm

Saturday, June 22nd at the Church of St. Luke & Matthew  
520 Clinton Avenue, Brooklyn, NY 11238  
10am to 11:30am

Come dressed to spend time outside and get hands-on training. Children are welcome and need to be accompanied by an adult. This event is rain or shine.

For more information or to register for a workshop, visit our website at [www.milliontreesnyc.org/care](http://www.milliontreesnyc.org/care) and click on the link "Learn more and sign up here", or email [stewards@milliontreesnyc.org](mailto:stewards@milliontreesnyc.org), or call (212) 360-TREE (212-360-8733).

### ❖ Wednesday, June 19<sup>th</sup>

- Hope Gardens Houses
- 422 Central Avenue, Brooklyn
- 6:30-8:30PM

### ❖ Saturday, June 22<sup>nd</sup>

- Church of St. Luke and St. Matthew
- 520 Clinton Avenue, Brooklyn
- 10-11:30AM