

**PROPOSED SHAFT 33B TO CITY WATER TUNNEL NO. 3
MANHATTAN LEG—STAGE 2**

CEQR No. 05DEP010M

Prepared by: New York City Department of Environmental Protection

Commissioner: **Emily Lloyd**

Lead Agency Contact: Angela Licata
Deputy Commissioner
Bureau of Environmental Planning and Assessment
New York City Department of Environmental Protection
59-17 Junction Boulevard
Flushing, NY 11373
(718) 595-4413

With the assistance of: AKRF, Inc.
Malcolm Pirnie, Inc.
Philip Habib & Associates
TRC Environmental Corporation
Eugene Boesch

January 20, 2006

TABLE OF CONTENTS

FOREWORD

CHAPTER 1: EXECUTIVE SUMMARY

1.1 Introduction.....	1-1
1.2 Purpose and Need and Project Overview.....	1-3
1.2.1 Introduction and Project Identification.....	1-3
1.2.2 Project Purpose and Need.....	1-4
Need for Shaft 33B.....	1-4
1.2.3 Proposed Location for Shaft 33B	1-5
1.2.4 Sites Evaluated in this EIS	1-6
Preferred Shaft Site and Water Main Connections.....	1-7
Alternative Sites and Water Main Connections	1-8
Other Alternatives	1-10
1.2.5 Overview of Shaft Site and Water Main Components	1-10
Shaft	1-10
Water Main Connections.....	1-11
1.2.6 Description of Construction Activity	1-11
Shaft Site Construction.....	1-11
Water Main Construction	1-16
Overall Construction Schedule.....	1-17
Activation.....	1-17
1.2.7 Operation and Maintenance.....	1-18
1.2.8 Potential Permits and Approvals	1-18
1.3 Summary of Potential Significant or Temporary Adverse Impacts—Shaft Sites.....	1-19
1.3.1 Introduction	1-19
1.3.2 Preferred Shaft Site	1-19
1.3.3 E. 59 th Street/Second Avenue Shaft Site	1-23
1.3.4 E. 61 st Street Shaft Site.....	1-25
1.3.5 E. 54 th Street/Second Avenue Shaft Site	1-27
1.4 Summary of Potential Significant or Temporary Adverse Impacts—Water Mains.....	1-30
1.4.1 Introduction.....	1-30
Urban Design and Visual Resources	1-30
Traffic.....	1-32
Noise	1-39
1.5 Summary of Other Alternatives.....	1-40
1.5.1 No Action Alternative	1-40
1.5.2 Water Main Only Alternative.....	1-40

TABLE OF CONTENTS

LIST OF TABLES

1.2-1 Shaft Construction Stages..... 1-13
1.2-2 Estimated Months of Construction, Water Main Connection Routes for Shaft Sites 1-17
1.3-1 Most Notable Significant or Temporary Adverse Construction Impacts Potential Shaft Sites..... 1-20
1.4-1 Most Notable Significant or Temporary Adverse Construction Impacts Water Main Connection Routes 1-31
1.4-2 Number of Street Trees Potentially Affected Water Main Connection Routes for Shaft Sites..... 1-32
1.4-3 Water Main Connections to Preferred Shaft Site Summary of Temporary Adverse Traffic Impacts..... 1-35

LIST OF FIGURES

1.1-1 Shaft Site Locations..... 1-7
1.1-2 Potential Water Main Connection Routes 1-7

CHAPTER 2: PURPOSE AND NEED AND PROJECT OVERVIEW

2.1 Introduction and Project Identification 2-1
2.2 Project Purpose and Need 2-2
 2.2.1 New York City’s Water Supply and Distribution System 2-2
 Aqueducts and Balancing Reservoirs 2-3
 Tunnels 2-3
 Local Distribution System 2-5
 2.2.2 Need for Shaft 33B 2-6
 Water Supply Issues in MIPZ and NIPZ 2-6
 Shaft 33B 2-7
2.3 Proposed Location for Shaft 33B 2-8
 2.3.1 Locational Requirements for Shaft 33B 2-8
 2.3.2 Review of Potential Sites 2-9
 2.3.3 Sites Evaluated in this EIS..... 2-10
 Preferred Shaft Site and Water Main Connections 2-11
 Alternative Sites and Water Main Connections 2-12
 Other Alternatives..... 2-14
2.4 Overview of Shaft Site and Water Main Components..... 2-14
 2.4.1 Shaft..... 2-14
 2.4.2 Water Main Connections 2-15
2.5 Description of Construction Activity 2-17
 2.5.1 Shaft Site Construction 2-17
 Overview 2-17
 Construction Stages 2-19
 2.5.2 Water Main Construction 2-26
 2.5.3 Overall Construction Schedule 2-28
2.6 Activation 2-29

TABLE OF CONTENTS

2.7 Operation and Maintenance.....2-30

2.8 Permits and Approvals.....2-31

 2.8.1 Permits and Approvals for Shaft 33B..... 2-31

 2.8.2 Water Main Approvals..... 2-32

2.9 Environmental Review2-32

2.10 Organization of this EIS2-34

LIST OF TABLES

2-1 Shaft Construction Stages..... 2-20

2-2 Anticipated Shaft Construction Schedule for Preferred Shaft Site 2-28

LIST OF FIGURES

2-1 New York City Water Supply System.....2-2

2-2 New York City Water Supply Tunnel System.....2-4

2-3 Manhattan Leg Tunnel and Shafts2-4

2-4 Pressure Zones.....2-5

2-5 Alternative Site Locations and Water Main Routes.....2-10

2-6 Alternative Site Locations and Water Main Routes.....2-10

2-7 Alternative Site Locations and Water Main Routes2-10

2-6 Shaft Profile.....2-15

2-7 Air Vent.....2-15

CHAPTER 3: IMPACT METHODOLOGIES

3.1 Introduction.....3.1-1

3.2 Land Use and Community Facilities, Zoning, and Public Policy.....3.2-1

 3.2.1 Introduction..... 3.2-1

 3.2.2 Existing Conditions Methodology..... 3.2-1

 Land Use and Community Facilities 3.2-2

 Zoning and Public Policy 3.2-2

 3.2.3 Future Conditions Without the Project Methodology 3.2-3

 3.2.4 Future Conditions With the Project Methodology..... 3.2-4

3.3 Open Space3.3-1

 3.3.1 Introduction..... 3.3-1

 3.3.2 Existing Conditions Methodology..... 3.3-2

 400-Foot Study Areas..... 3.3-2

 ¼-Mile Study Area for the Preferred Shaft Site 3.3-3

 3.3.3 Future Conditions Without the Project Methodology 3.3-5

 3.3.4 Future Conditions With the Project Methodology..... 3.3-5

TABLE OF CONTENTS

3.4 Socioeconomic Conditions	3.4-1
3.4.1 Introduction	3.4-1
3.4.2 Existing Conditions Methodology.....	3.4-1
Residents and Businesses	3.4-1
Water and Sewer Rates.....	3.4-2
3.4.3 Future Conditions Without the Project Methodology.....	3.4-2
Residents and Businesses	3.4-2
Water and Sewer Rates.....	3.4-2
3.4.4 Future Conditions With the Project Methodology.....	3.4-2
Residents and Businesses	3.4-2
Water and Sewer Rates.....	3.4-3
3.5 Historic Resources	3.5-1
3.5.1 Introduction	3.5-1
3.5.2 Existing Conditions Methodology.....	3.5-2
Establishing Study Areas.....	3.5-2
Identification of Existing Historic Resources	3.5-2
3.5.3 Future Conditions Without the Project Methodology.....	3.5-4
3.5.4 Future Conditions With the Project Methodology.....	3.5-4
3.6 Urban Design and Visual Resources	3.6-1
3.6.1 Introduction	3.6-1
3.6.2 Existing Conditions Methodology.....	3.6-2
3.6.3 Future Conditions Without the Project Methodology.....	3.6-2
3.6.4 Future Conditions With the Project Methodology.....	3.6-2
3.7 Neighborhood Character	3.7-1
3.7.1 Introduction	3.7-1
3.7.2 Existing Conditions Methodology.....	3.7-2
3.7.3 Future Conditions Without the Project Methodology.....	3.7-2
3.7.4 Future Conditions With the Project Methodology.....	3.7-3
3.8 Infrastructure and Energy	3.8-1
3.8.1 Introduction	3.8-1
3.8.2 Existing Conditions Methodology.....	3.8-1
3.8.3 Future Conditions Without the Project Methodology.....	3.8-1
3.8.4 Future Conditions With the Project Methodology.....	3.8-1
Construction	3.8-1
Operation	3.8-2
3.9 Traffic and Parking	3.9-1
3.9.1 Introduction	3.9-1
Project Construction and Study Areas	3.9-1
3.9.2 Existing Conditions Methodology.....	3.9-3
Traffic Operations Analysis.....	3.9-4
Parking Analysis.....	3.9-5

TABLE OF CONTENTS

Safety Analysis.....	3.9-5
3.9.3 Future Conditions Without the Project Methodology	3.9-5
Traffic Operations Analysis	3.9-6
Parking Analysis	3.9-6
Safety Analysis.....	3.9-6
3.9.4 Future Conditions With the Project Methodology.....	3.9-6
Construction	3.9-6
Operation.....	3.9-8
3.10 Transit and Pedestrians.....	3.10-1
3.10.1 Introduction.....	3.10-1
Project Construction and Study Areas.....	3.10-1
3.10.2 Existing Conditions Methodology	3.10-3
Transit Analysis.....	3.10-3
Pedestrian Operations Analysis.....	3.10-3
3.10.3 Future Conditions Without the Project Methodology	3.10-5
Transit Analysis.....	3.10-5
Pedestrian Operations Analysis.....	3.10-6
3.10.4 Future Conditions With the Project Methodology.....	3.10-6
Construction	3.10-6
Operation.....	3.10-7
3.11 Air Quality	3.11-1
3.11.1 Introduction	3.11-1
3.11.2 Pollutants For Analysis	3.11-2
Carbon Monoxide.....	3.11-2
Nitrogen Oxides, Volatile Organic Compounds and Ozone.....	3.11-2
Lead.....	3.11-3
Respirable Particulate Matter—PM ₁₀ and PM _{2.5}	3.11-3
Sulfur Dioxide	3.11-4
Summary	3.11-4
3.11.3 Air Quality Standards, Plans, and Thresholds Guidance.....	3.11-4
National and State Air Quality Standards.....	3.11-5
NAAQS Attainment Status and State Implementation Plans	3.11-5
Incremental Air Quality Thresholds.....	3.11-7
3.11.4 Existing Conditions	3.11-8
3.11.5 Future Conditions Without the Project Methodology	3.11-9
Mobile Sources.....	3.11-9
Stationary Construction Sources	3.11-13
3.11.6 Future Conditions With the Project Methodology.....	3.11-13
Shaft Sites.....	3.11-13
Water Main Connections.....	3.11-20
Operation.....	3.11-26

TABLE OF CONTENTS

3.12 Noise	3.12-1
3.12.1 Introduction	3.12-1
3.12.2 Noise Impact Thresholds	3.12-1
Perception of Noise	3.12-1
Noise Descriptors	3.12-2
Applicable Noise Criteria	3.12-3
3.12.3 Existing Conditions Methodology	3.12-3
3.12.4 Future Conditions Without the Project Methodology	3.12-4
3.12.5 Future Conditions With the Project Methodology	3.12-4
Blasting	3.12-4
Other Construction Activities	3.12-4
Operation	3.12-9
3.13 Vibration	3.13-1
3.13.1 Introduction	3.13-1
Types of Vibration Impacts	3.13-1
3.13.2 Existing Conditions Methodology	3.13-2
3.13.3 Future Conditions Without the Project Methodology	3.13-3
3.13.4 Future Conditions With the Project Methodology	3.13-3
Blasting	3.13-3
Other Construction Activities	3.13-3
3.14 Hazardous Materials	3.14-1
3.14.1 Introduction	3.14-1
3.14.2 Existing Conditions Methodology	3.14-1
Phase I Environmental Site Assessments	3.14-1
Phase II Environmental Site Assessment for the Preferred Shaft Site	3.14-2
3.14.3 Future Conditions Without the Project Methodology	3.14-3
3.14.4 Future Conditions With the Project Methodology	3.14-3
3.15 Public Health	3.15-1
3.15.1 Introduction	3.15-1
3.15.2 Existing Conditions Methodology	3.15-1
Impact Assessment	3.15-2
3.15.3 Future Conditions Without the Project Methodology	3.15-4
3.15.4 Future Conditions With the Project Methodology	3.15-4
Air Quality	3.15-4
Noise	3.15-5
Traffic	3.15-5
Hazardous Materials	3.15-5

LIST OF TABLES

3.9-1	Traffic Level of Service Definitions	3.9-4
3.10-1	Level of Service Criteria for Pedestrian Elements	3.10-5

TABLE OF CONTENTS

3.11-1 Ambient Air Quality Standards 3.11-6

3.11-2 Mobile Source Analysis Intersection Locations 3.11-12

3.11-3 Example of Estimated Construction Equipment Data for Preferred Shaft Site 3.11-15

3.11-4 Estimated Minimum Particulate Matter (PM) Control for Shaft Site Construction Equipment 3.11-17

3.11-5 Background Air Quality Data for Analyses 3.11-20

3.11-6 Water Main Connections Construction Equipment Data 3.11-22

3.11-7 Estimated Minimum Particulate Matter (PM) Control for Water Main Construction Equipment 3.11-24

3.12-1 Utility Noise Levels of Common Sources 3.12-2

3.12-2 Average Ability to Perceive Changes in Noise Levels 3.12-3

3.12-3 Shaft Site Construction Equipment and Noise Levels 3.12-7

3.12-4 Water Main Construction Equipment and Noise Levels 3.12-8

3.13-1 Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Shaft Site
Construction 3.13-4

3.13-2 Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Water Main
Construction 3.13-4

3.14-1 Hazardous Materials Classifications 3.14-4

LIST OF FIGURES

3.9-1 Preferred Shaft Site and Water Main Connections Traffic Study Areas3.9-2

3.9-2 E. 54th Street/Second Avenue Shaft Site Traffic Study Area3.9-3

CHAPTER 4: PREFERRED SHAFT SITE

4.1 Project Description4.1-1

4.1.1 Introduction 4.1-1

4.1.2 Description of the Preferred Shaft Site 4.1-1

4.1.3 Location of Shaft Components on the Preferred Shaft Site 4.1-2

4.1.4 Description of Construction at the Preferred Shaft Site 4.1-3

Construction Activity 4.1-3

Site Layout 4.1-7

Construction Equipment 4.1-9

Construction Schedule 4.1-9

4.1.5 Operation 4.1-10

4.1.6 Permits and Approvals 4.1-10

4.2 Land Use And Community Facilities, Zoning, And Public Policy4.2-1

4.2.1 Introduction 4.2-1

4.2.2 Existing Conditions 4.2-1

Land Use 4.2-1

Community Facilities 4.2-3

Zoning 4.2-4

Public Policy 4.2-5

TABLE OF CONTENTS

4.2.3	Future Conditions Without the Project	4.2-7
	Land Use and Community Facilities	4.2-7
4.2.4	Future Conditions With the Project	4.2-9
	Construction	4.2-9
	Activation and Operation	4.2-15
4.3	Open Space	4.3-1
4.3.1	Introduction	4.3-1
4.3.2	Existing Conditions	4.3-1
	Preferred Shaft Site	4.3-1
	400-Foot Study Area	4.3-2
	¼-Mile Study Area	4.3-4
4.3.3	Future Conditions Without the Project	4.3-8
	400-Foot Study Area	4.3-8
	¼-Mile Study Area	4.3-9
4.3.4	Future Conditions With the Project	4.3-11
	Construction	4.3-11
	Operation	4.3-17
4.4	Socioeconomic Conditions	4.4-1
4.4.1	Introduction	4.4-1
4.4.2	Existing Conditions	4.4-1
	Residents and Businesses in the Vicinity of the Preferred Shaft Site	4.4-1
	Water and Sewer Rates	4.4-2
4.4.3	Future Conditions Without the Project	4.4-4
	Residents and Businesses in the Vicinity of the Preferred Shaft Site	4.4-4
	Water and Sewer Rates	4.4-4
4.4.4	Future Conditions with the Project	4.4-4
	Residents and Businesses in the Vicinity of the Preferred Shaft Site	4.4-5
	Water and Sewer Rates	4.4-6
4.5	Historic Resources	4.5-1
4.5.1	Introduction	4.5-1
4.5.2	Existing Conditions	4.5-1
	Archaeological Resources	4.5-1
	Architectural Resources	4.5-4
4.5.3	Future Conditions Without the Project	4.5-5
	Archaeological Resources	4.5-5
	Architectural Resources	4.5-6
4.5.4	Future Conditions With the Project	4.5-6
	Construction	4.5-6
	Operation	4.5-8
4.6	Urban Design And Visual Resources	4.6-1
4.6.1	Introduction	4.6-1

TABLE OF CONTENTS

4.6.2	Existing Conditions	4.6-1
	Urban Design.....	4.6-1
	Visual Resources	4.6-3
4.6.3	Future Conditions Without the Project.....	4.6-3
	Urban Design.....	4.6-3
	Visual Resources	4.6-4
4.6.4	Future Conditions With the Project.....	4.6-5
	Construction	4.6-5
	Operation.....	4.6-8
4.7	Neighborhood Character	4.7-1
4.7.1	Introduction	4.7-1
4.7.2	Existing Conditions	4.7-1
	Preferred Shaft Site	4.7-1
	Study Area.....	4.7-2
4.7.3	Future Conditions Without the Project.....	4.7-3
4.7.4	Future Conditions With the Project.....	4.7-4
	Construction	4.7-4
	Operation.....	4.7-5
4.8	Infrastructure and Energy	4.8-1
4.8.1	Introduction	4.8-1
4.8.2	Existing Conditions	4.8-1
4.8.3	Future Conditions Without the Project.....	4.8-1
4.8.4	Future Conditions With the Project.....	4.8-2
	Construction	4.8-2
	Operation.....	4.8-4
4.9	Traffic and Parking.....	4.9-1
4.9.1	Introduction	4.9-1
4.9.2	Existing Conditions	4.9-1
	Study Area Roadways and Traffic Volumes	4.9-1
	Traffic Operations Analysis	4.9-3
	Parking Analysis	4.9-5
	Safety Analysis.....	4.9-6
4.9.3	Future Conditions Without the Project.....	4.9-7
	Parking Analysis	4.9-7
	Safety Analysis.....	4.9-7
4.9.4	Future Conditions With the Project.....	4.9-9
	Construction	4.9-9
	Operation.....	4.9-17
4.9.5	Conclusion.....	4.9-18
4.10	Transit and Pedestrians	4.10-1
4.10.1	Introduction	4.10-1

TABLE OF CONTENTS

4.10.2 Existing Conditions	4.10-1
Transit Analysis.....	4.10-1
Pedestrian Operations Analysis	4.10-2
4.10.3 Future Conditions Without the Project	4.10-2
Transit Analysis.....	4.10-2
Pedestrian Operations Analysis	4.10-3
4.10.4 Future Conditions With the Project	4.10-5
Construction	4.10-5
Operation	4.10-8
4.10.5 Conclusion.....	4.10-9
4.11 Air Quality	4.11-1
4.11.1 Introduction	4.11-1
4.11.2 Existing Conditions	4.11-1
Existing Monitored Air Quality Conditions (2004).....	4.11-1
4.11.3 Future Conditions Without the Project	4.11-2
4.11.4 Future Conditions With the Project	4.11-3
Construction	4.11-3
Operation	4.11-8
4.12 Noise	4.12-1
4.12.1 Introduction	4.12-1
4.12.2 Existing Conditions	4.12-1
Monitoring Locations	4.12-1
Monitoring Results	4.12-2
4.12.3 Future Conditions Without the Project	4.12-2
4.12.4 Future Conditions With the Project	4.12-3
Construction	4.12-3
Activation and Operation.....	4.12-15
4.13 Vibration.....	4.13-1
4.13.1 Introduction	4.13-1
4.13.2 Existing Conditions	4.13-1
4.13.3 Future Conditions Without the Project	4.13-2
4.13.4 Future Conditions With the Project	4.13-2
Construction	4.13-2
Operation	4.13-9
4.14 Hazardous Materials.....	4.14-1
4.14.1 Introduction	4.14-1
4.14.2 Existing Conditions	4.14-1
Current Site Conditions	4.14-1
Adjacent and Vicinity Land Uses	4.14-2
Geology and Hydrogeology.....	4.14-2
Records Search	4.14-2

TABLE OF CONTENTS

Historical Uses of the Preferred Shaft Site and Adjacent Properties.....	4.14-4
Phase II Environmental Site Assessment	4.14-5
4.14.3 Future Conditions Without the Project.....	4.14-9
4.14.4 Future Conditions With the Project.....	4.14-9
Construction	4.14-9
Activation and Operation	4.14-13
4.15 Public Health	4.15-1
4.15.1 Introduction.....	4.15-1
4.15.2 Existing Conditions	4.15-1
Health Effects Related to Emissions of Particulate Matter.....	4.15-2
4.15.3 Future Conditions Without the Project.....	4.15-14
4.15.4 Future Conditions With the Project.....	4.15-14
Construction	4.15-14
Operation.....	4.15-18
4.16 Mitigation Measures.....	4.16-1
4.16.1 Introduction	4.16-1
4.16.2 Noise	4.16-1
4.17 Unavoidable Adverse Impacts.....	4.17-1

LIST OF TABLES

4.1-1 Summary of Shaft Construction Stages at Preferred Shaft Site	4.1-5
4.1-2 Preferred Shaft Site Average Equipment Usage Assumptions for Construction.....	4.1-10
4.2-1 Zoning Districts in the Study Area.....	4.2-5
4.3-1 Results of User Surveys	4.3-2
4.3-2 Population in the ¼-Mile Study Area.....	4.3-5
4.3-3 Open Spaces in the ¼-Mile Study Area	4.3-6
4.3-4 Open Space Ratios in the ¼-Mile Study Area.....	4.3-8
4.3-5 Open Space Ratios in the ¼-Mile Study Area—Future Without the Project	4.3-10
4.3-6 Open Space Ratios in the ¼-Mile Study Area—Future With the Project	4.3-16
4.5-1 Architectural Resources Within the Preferred Shaft Site Study Area	4.5-4
4.8-1 Utility Lines Located on East 59 th Street Between First and Second Avenues	4.8-1
4.9-1 2004 Existing Conditions – Preferred Shaft Site Study Area.....	4.9-4
4.9-2 Accident Data.....	4.9-6
4.9-3 2008 No Build and 2004 Existing Conditions Comparison—Preferred Shaft Site Study Area	4.9-8
4.9-4 2008 Build and No Build Conditions Comparison—Preferred Shaft Site Study Area	4.9-13
4.10-1 2004 Existing Conditions: Pedestrian LOS Analysis for Sidewalks	4.10-3
4.10-2 2004 Existing Conditions: Pedestrian LOS Analysis for Corner Reservoirs	4.10-3
4.10-3 2004 Existing Conditions: Pedestrian LOS Analysis for Crosswalks	4.10-4
4.10-4 2008 No Build Conditions: Pedestrian LOS Analysis for Sidewalks.....	4.10-4
4.10-5 2008 No Build Conditions: Pedestrian LOS Analysis for Corner Reservoirs	4.10-5
4.10-6 2008 No Build Conditions: Pedestrian LOS Analysis for Crosswalks.....	4.10-5

TABLE OF CONTENTS

4.10-7	2008 Build Conditions: Pedestrian LOS Analysis for Sidewalks.....	4.10-7
4.10-8	2008 Build Conditions: Pedestrian LOS Analysis for Corner Reservoirs.....	4.10-7
4.10-9	2008 Build Conditions: Pedestrian LOS Analysis for Crosswalks.....	4.10-8
4.11-1	Representative Monitored Ambient Air Quality Data (2004)	4.11-2
4.11-2	On-Site Construction Equipment for Peak Short-Term and Annual Period.....	4.11-4
4.11-3	Construction Equipment Data	4.11-6
4.11-4	Results of Dispersion Analysis for Construction Activities at the Preferred Shaft Site	4.11-7
4.12-1	Baseline Ambient Noise Monitoring Results for the Preferred Shaft Site	4.12-2
4.12-2	Identification and Description of Selected Shaft Receptor Locations	4.12-5
4.12-3	Noise Levels—Average Workday.....	4.12-8
4.12-4	Noise Levels—Peak Hour	4.12-10
4.13-1	Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Shaft Site Construction.....	4.13-6
4.13-2	Building Classification Guidelines (the Swiss Standard)	4.13-8
4.14-1	Preferred Shaft 33B Site Soil Sampling Results- Compounds Detected	4.14-6
4.14-2	Preferred Shaft 33B Site Groundwater Sampling Results	4.14-8
4.16-1	Comparison of Noise Levels With and Without 15 dBA Acoustical Enclosure	4.16-4

LIST OF FIGURES

4.1-1	E. 59 th Street and First Avenue Conceptual Site Layout	4.1-3
4.1-2	Base Configuration.....	4.1-7
4.1-3	Alternate Site Configuration.....	4.1-8
4.2-1	Land Use	4.2-1
4.2-2	Zoning	4.2-4
4.3-1	Public Open Spaces Within 400 Feet and ¼ Mile	4.3-2
4.3-2	Illustrative View of Typical Activities at the Multi-Use Area	4.3-3
4.5-1	Historic Resources.....	4.5-1
4.5-2	1901-1908 Construction of the Queensboro Bridge	4.5-4
4.6-1	Visual Resources	4.6-1
4.6-2	Photographs of Study Area.....	4.6-1
4.6-3	Photographs of Study Area.....	4.6-2
4.6-4	Photographs of Study Area.....	4.6-2
4.6-5	Photographs of Study Area.....	4.6-2
4.6-6	Photographs of Study Area.....	4.6-3
4.6-7	Photographs of Study Area.....	4.6-3
4.6-8	Illustrative Renderings of Construction Barrier.....	4.6-5
4.6-9	View of Example Shaft Site	4.6-5
4.6-10	Illustrative Rendering, Completed Shaft Features.....	4.6-8
4.9-1	2004 Existing Traffic Volume Network, Shaft Study Area AM Peak Hour	4.9-1
4.9-2	2004 Existing Traffic Volume Network, Shaft Study Area Midday Peak Hour	4.9-1
4.9-3	2004 Existing Traffic Volume Network, Shaft Study Area PM Peak Hour	4.9-1

TABLE OF CONTENTS

4.9-4	Queensboro Bridge Access Configurations.....	4.9-2
4.9-5	On-Street Parking Regulations (Map).....	4.9-5
4.9-6	On-Street Parking Regulations (Legend)	4.9-5
4.9-7	2008 No Build Traffic Volume Network, Shaft Study Area AM Peak Hour.....	4.9-7
4.9-8	2008 No Build Traffic Volume Network, Shaft Study Area Midday Peak Hour.....	4.9-7
4.9-9	2008 No Build Traffic Volume Network, Shaft Study Area PM Peak Hour	4.9-7
4.9-10	2008 Build Traffic Volume Network, Shaft Study Area AM Peak Hour.....	4.9-9
4.9-11	2008 Build Traffic Volume Network, Shaft Study Area Midday Peak Hour.....	4.9-9
4.9-12	2008 Build Traffic Volume Network, Shaft Study Area PM Peak Hour	4.9-9
4.10-1	2004 Existing Pedestrian Volumes Shaft Study Area	4.10-1
4.11-1	Predicted 24-Hour PM _{2.5} Concentrations for Construction Activities.....	4.11-4
4.12-1	Noise Monitoring Locations.....	4.12-1
4.12-2	Noise Receptor Locations	4.12-5
4.13-1	Vibration Measurement Locations	4.13-1
4.14-1	Environmental Sampling Locations	4.14-5

CHAPTER 5: WATER MAIN CONNECTIONS

5.1	Project Description.....	5.1-1
5.1.1	Introduction.....	5.1-1
5.1.2	Issues that Affect Water Main Construction	5.1-1
5.1.3	Water Main Connection Routes	5.1-4
	First Avenue Route (Reasonable Worst-Case Route)	5.1-5
	Sutton Place Route (Additional Representative Route).....	5.1-5
	E. 59 th Street/E. 61 st Street Route (Additional Representative Route)	5.1-6
	Alternative Shaft Site Water Main Connection Options	5.1-6
5.1.4	Water Main Construction	5.1-6
	Construction Methods	5.1-6
	Water Main Construction Options.....	5.1-12
	Estimated Construction Schedule.....	5.1-16
5.1.5	Required Permits and Approvals.....	5.1-18
5.2	Land Use and Community Facilities, Zoning, and Public Policy.....	5.2-1
5.2.1	Introduction.....	5.2-1
5.2.2	Existing Conditions	5.2-1
	Land Use	5.2-1
	Community Facilities	5.2-3
	Zoning and Public Policy	5.2-4
5.2.3	Future Conditions Without the Project.....	5.2-6
	Land Use and Community Facilities	5.2-6
	Zoning and Public Policy	5.2-7
5.2.4	Future Conditions With the Project.....	5.2-8
	Construction	5.2-8

TABLE OF CONTENTS

Operation	5.2-12
5.3 Open Space.....	5.3-1
5.3.1 Introduction	5.3-1
5.3.2 Existing Conditions	5.3-1
First Avenue Route	5.3-1
Sutton Place Route.....	5.3-4
E. 59 th Street/E. 61 st Street Route	5.3-4
5.3.3 Future Conditions Without the Project	5.3-4
5.3.4 Future Conditions With the Project	5.3-5
Construction	5.3-5
Operation	5.3-8
5.4 Socioeconomic Conditions.....	5.4-1
5.4.1 Introduction	5.4-1
5.4.2 Existing Conditions	5.4-1
Residents and Businesses in the Vicinity of the Water Main Routes.....	5.4-1
5.4.3 Future Conditions Without the Project	5.4-2
Residents and Businesses in the Vicinity of the Water Main Routes	5.4-2
5.4.4 Future Conditions with the Project.....	5.4-2
Residents and Businesses in the Vicinity of the Water Main Routes	5.4-2
5.5 Historic Resources	5.5-1
5.5.1 Introduction	5.5-1
5.5.2 Existing Conditions	5.5-1
Archaeological Resources	5.5-1
Architectural Resources.....	5.5-4
5.5.3 Future Conditions Without the Project	5.5-6
Archaeological Resources	5.5-6
Architectural Resources.....	5.5-6
5.5.4 Future Conditions With the Project	5.5-7
Construction	5.5-7
Operation	5.5-10
5.6 Urban Design and Visual Resources	5.6-1
5.6.1 Introduction	5.6-1
5.6.2 Existing Conditions	5.6-1
Urban Design.....	5.6-1
Visual Resources	5.6-3
5.6.3 Future Conditions Without the Project	5.6-4
Urban Design.....	5.6-4
Visual Resources	5.6-4
5.6.4 Future Conditions With the Project	5.6-4
Construction	5.6-4
Urban Design.....	5.6-5

TABLE OF CONTENTS

Visual Resources.....	5.6-7
Operation.....	5.6-8
5.7 Neighborhood Character	5.7-1
5.7.1 Introduction.....	5.7-1
5.7.2 Existing Conditions.....	5.7-1
First Avenue Route.....	5.7-1
Sutton Place Route.....	5.7-3
E. 59 th Street/E. 61 st Street Route.....	5.7-4
5.7.3 Future Conditions Without the Project.....	5.7-5
5.7.4 Future Conditions With the Project.....	5.7-6
Construction.....	5.7-6
Operation.....	5.7-8
5.8 Infrastructure and Energy.....	5.8-1
5.8.1 Introduction.....	5.8-1
5.8.2 Existing Conditions.....	5.8-1
5.8.3 Future Conditions Without the Project.....	5.8-1
5.8.4 Future Conditions With the Project.....	5.8-2
Construction.....	5.8-2
Operation.....	5.8-4
5.9 Traffic and Parking.....	5.9-1
5.9.1 Introduction.....	5.9-2
First Avenue Route.....	5.9-2
Sutton Place Route.....	5.9-2
E. 59 th Street/E. 61 st Street Route.....	5.9-2
5.9.2 Existing Conditions.....	5.9-3
First Avenue Route Base Scenario.....	5.9-3
Sutton Place Route.....	5.9-7
E. 59 th Street/E. 61 st Street Route.....	5.9-10
5.9.3 Future Conditions Without the Project.....	5.9-13
First Avenue Route Base Scenario.....	5.9-13
Sutton Place Route.....	5.9-15
E. 59 th Street/E. 61 st Street Route.....	5.9-15
5.9.4 Future Conditions With the Project.....	5.9-18
First Avenue Route Base Scenario.....	5.9-18
Sutton Place Route.....	5.9-29
E. 59 th Street/E. 61 st Street Route.....	5.9-37
5.9.5 Water Main Connection Construction Options.....	5.9-44
Scenario A.....	5.9-44
Scenario B.....	5.9-46
Scenario C.....	5.9-46
5.9.6 Conclusions.....	5.9-46

TABLE OF CONTENTS

5.10 Transit and Pedestrians	5.10-1
5.10.1 Introduction	5.10-1
First Avenue Route	5.10-1
Sutton Place Route.....	5.10-2
E. 59 th Street/E. 61 st Street Route	5.10-2
5.10.2 Existing Conditions	5.10-3
Transit Analysis.....	5.10-3
Pedestrian Operations Analysis	5.10-4
5.10.3 Future Conditions Without the Project	5.10-4
Transit Analysis.....	5.10-4
Pedestrian Operations Analysis	5.10-5
5.10.4 Future Conditions With the Project	5.10-6
First Avenue Route	5.10-6
Sutton Place Route.....	5.10-9
E. 59 th Street/E. 61 st Street Route	5.10-10
5.10.5 Conclusions	5.10-11
5.11 Air Quality	5.11-1
5.11.1 Introduction	5.11-1
5.11.2 Existing Conditions	5.11-2
Existing Monitored Air Quality Conditions (2004).....	5.11-2
Background Data for Criteria Pollutants	5.11-2
5.11.3 Future Conditions Without the Project	5.11-2
Mobile Sources.....	5.11-2
Stationary Sources	5.11-4
5.11.4 Future Conditions With the Project	5.11-5
Construction	5.11-5
5.12 Noise	5.12-1
5.12.1 Introduction	5.12-1
5.12.2 Existing Conditions	5.12-1
First Avenue Route	5.12-1
Sutton Place Route.....	5.12-3
E. 59 th Street/E. 61 st Street Route	5.12-4
5.12.3 Future Conditions Without the Project	5.12-5
5.12.4 Future Conditions With the Project	5.12-5
Sensitive Receptors used in the Analysis	5.12-5
Scenarios Analyzed	5.12-5
Measures to Reduce Noise at the Site.....	5.12-6
Potential Noise Impacts	5.12-6
Conclusions	5.12-27
5.13 Vibration.....	5.13-1
5.13.1 Introduction	5.13-1

TABLE OF CONTENTS

5.13.2	Future Conditions With the Project.....	5.13-1
	Construction	5.13-1
	Operation.....	5.13-3
5.14	Hazardous Materials.....	5.14-1
5.14.1	Introduction	5.14-1
5.14.2	Existing Conditions	5.14-1
	Current Conditions	5.14-1
	Adjacent and Vicinity Land Uses.....	5.14-2
	Geology/Hydrogeology	5.14-2
	Records Search.....	5.14-2
	Sanborn/ Fire Insurance Maps.....	5.14-4
5.14.3	Future Conditions Without the Project.....	5.14-6
5.14.4	Future Conditions With the Project.....	5.14-6
	Construction	5.14-6
	Activation and Operation	5.14-7
5.15	Public Health	5.15-1
5.15.1	Introduction	5.15-1
5.15.2	Existing Conditions	5.15-1
5.15.3	Future Conditions Without the Project.....	5.15-1
5.15.4	Future Conditions With the Project.....	5.15-2
	Construction	5.15-2
	Operation.....	5.15-5
5.16	Mitigation Measures.....	5.16-1
5.16.1	Introduction	5.16-1
5.16.2	Traffic and Parking.....	5.16-1
5.16.3	Air	5.16-21

LIST OF TABLES

5.1-1	Potential Staging Plan for First Avenue Route (Reasonable Worst-Case Route)	5.1-8
5.1-2	Water Main Construction Summary.....	5.1-9
5.1-3	Equipment Usage Assumptions for Construction of Water Main Connections	5.1-10
5.1-4	Water Main Connection Routes and Construction Scenarios.....	5.1-13
5.1-5	Estimated Construction Schedule for First Avenue Route (Reasonable Worst-Case Route), Base Scenario	5.1-17
5.2-1	Community Facilities in the Study Area	5.2-4
5.2-2	Zoning Districts in the Study Area.....	5.2-5
5.3-1	Open Spaces in the 400-Foot Study Area for Water Main Connections	5.3-2
5.3-2	Results of Open Space User Surveys	5.3-3
5.5-1	Architectural Resources Within the Water Main Connection Study Areas.....	5.5-4
5.6-1	Trees and Street Furniture Potentially Affected by Water Main Construction Preferred Shaft Site	5.6-5
5.9-1	2004 Existing Conditions—First Avenue Route Water Main Connection Study Area.....	5.9-5
5.9-2	2004 Existing Conditions—Sutton Place Route Water Main Connection Study Area	5.9-9

TABLE OF CONTENTS

5.9-3	2004 Existing Conditions—E. 59 th /E. 61 st Street Route Water Main Connection Study Area.....	5.9-12
5.9-4	2008 No Build and 2004 Existing Conditions Comparison—First Avenue Route Water Main Connection Study Area	5.9-14
5.9-5	2008 No Build and 2004 Existing Conditions Comparison—Sutton Place Route Water Main Connection Study Area	5.9-16
5.9-6	2008 No Build and 2004 Existing Conditions Comparison—E. 59 th /E. 61 st Street Route Water Main Connection Study Area	5.9-17
5.9-7	2008 Build and No Build Conditions Comparison First Avenue Route Base Scenario Water Main Connection Study Area Segments 1 & 3	5.9-21
5.9-8	2008 Build and No Build Conditions Comparison First Avenue Route Base Scenario Water Main Connection Study Area Segments 5 & 7	5.9-22
5.9-9	2008 Build and No Build Conditions Comparison First Avenue Route Base Scenario Water Main Connection Study Area Segments 9 & 10	5.9-23
5.9-10	2008 Build and No Build Conditions Comparison Sutton Place Route Water Main Connection Study Area E. 59 th Street Segment	5.9-32
5.9-11	2008 Build and No Build Conditions Comparison Sutton Place Route Water Main Connection Study Area Segments 1 & 3	5.9-33
5.9-12	2008 Build and No Build Conditions Comparison Sutton Place Route Water Main Connection Study Area Segments 5 & 9	5.9-34
5.9-13	2008 Build and No Build Conditions Comparison E. 59 th Street/E. 61 st Street Route Water Main Connection Study Area Segments 1, 3, & 5	5.9-41
5.9-14	2008 Build and No Build Conditions Comparison E. 59 th Street/E. 61 st Street Route Water Main Connection Study Area Segments 6 & 8	5.9-42
5.9-15	2008 Scenario A Build Conditions, Midday Peak Period—Water Main Connection Study Area Segments 1 & 3	5.9-45
5.9-16	Water Main Connections to Preferred Shaft Site Summary of Temporary Adverse Traffic Impacts	5.9-49
5.10-1	2004 Existing Conditions: Sidewalk LOS Analysis	5.10-5
5.10-2	2008 No Build Conditions: Sidewalk LOS Analysis.....	5.10-6
5.10-3	2008 First Avenue Route Scenario A Build Conditions: Sidewalk LOS Analysis.....	5.10-8
5.10-4	2008 E. 59 th Street/E. 61 st Street Route Build Conditions: Sidewalk LOS Analysis.....	5.10-10
5.11-1	Total Maximum Predicted 8-Hour Average CO Concentrations (ppm) Future Without the Project (2008)	5.11-3
5.11-2	Maximum Total Predicted PM Concentrations ($\mu\text{g}/\text{m}^3$) Future Without the Project 2008.....	5.11-4
5.11-3	Maximum Predicted 8-Hour Average CO Concentrations (ppm) Future Without and With the Proposed Project 2008 (Reasonable Worst Case Route—Base Scenario)	5.11-6
5.11-4	Maximum Predicted PM Total Concentrations ($\mu\text{g}/\text{m}^3$) Future With the Proposed Project 2008 (Reasonable Worst Case Route—Base Scenario)	5.11-7
5.11-5	Water Main On-Site Construction Equipment for Peak Short-Term and Annual Period.....	5.11-11
5.11-6	Results of Dispersion Analysis for Water Main Construction, Reasonable Worst Case Route Base Scenario	5.11-13
5.11-7	Results of Dispersion Analysis for Water Main Construction, Reasonable Worst-Case Route Scenario A	5.11-14
5.11-8	Water Main and Shaft Site On-Site Construction Equipment for Peak Short-Term and Annual Period.....	5.11-17
5.11-9	Results of Dispersion Analysis for Combined Water Main and Stage 3 Construction, Reasonable Worst Case Route—Base Scenario	5.11-18

TABLE OF CONTENTS

5.11-10	Results of Dispersion Analysis for Combined Water Main and Stage 3 Construction, Reasonable Worst Case Route—Scenario A.....	5.11-20
5.12-1	Baseline Ambient Noise Monitoring Results for the First Avenue Route	5.12-2
5.12-2	Baseline Ambient Noise Monitoring Results for the Sutton Place Route	5.12-3
5.12-3	Baseline Ambient Noise Monitoring Results for the E. 59 th Street/E. 61 st Street Route.....	5.12-4
5.12-4	Water Main Without Venturi - First Avenue, Average Analysis—Weekday and Weekend.....	5.12-14
5.12-5	Cross Street Analysis - First Avenue, Average Analysis—Weekday and Weekend	5.12-16
5.12-6	Water Main with Venturi Chamber - First Avenue, Average Analysis—Weekday and Weekend.....	5.12-18
5.12-7	Water Main Without Venturi - First Avenue, Peak Analysis—Weekday and Weekend	5.12-19
5.12-8	Cross Street Analysis - First Avenue Route, Peak Analysis—Weekday and Weekend.....	5.12-21
5.12-9	Water Main With Venturi - First Avenue, Peak Analysis—Weekday and Weekend	5.12-22
5.12-10	Sutton Place Without Venturi Chambers Analysis—Average Analysis	5.12-23
5.12-11	Sutton Place Without Venturi Chambers Analysis—Peak Analysis.....	5.12-24
5.12-12	E. 59 th Street/E. 61 st Street Cross Street Analysis—Average Analysis	5.12-25
5.12-13	E. 59 th Street/E. 61 st Street Cross Street Analysis—Peak Analysis.....	5.12-26
5.13-1	Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Water Main Construction	5.13-2
5.16-1	Conventional Mitigation Measures—First Avenue Route	5.16-2
5.16-2	2008 Mitigated Build, Build, and No Build Conditions Comparison First Avenue Route Water Main Connection Study Area—AM Peak Hour	5.16-4
5.16-3	2008 Mitigated Build, Build, and No Build Conditions Comparison First Avenue Route Water Main Connection Study Area—Midday Peak Hour	5.16-5
5.16-4	2008 Mitigated Build, Build, and No Build Conditions Comparison First Avenue Route Water Main Connection Study Area—PM Peak Hour	5.16-6
5.16-5	2008 Traffic Diversion and Mitigated Build Conditions Comparison—First Avenue Intersections	5.16-9
5.16-6	2008 Traffic Diversion and No Build Conditions Comparison – Sutton Place/York Avenue Intersections	5.16-10
5.16-7	Conventional Mitigation Measures—Sutton Place Route.....	5.16-12
5.16-8	2008 Mitigated Build, Build, and No Build Conditions Comparison Sutton Place Route Water Main Connection Study Area—AM Peak Hour	5.16-13
5.16-9	2008 Mitigated Build, Build, and No Build Conditions Comparison Sutton Place Route Water Main Connection Study Area—Midday Peak Hour	5.16-14
5.16-10	2008 Mitigated Build, Build, and No Build Conditions Comparison Sutton Place Route Water Main Connection Study Area—PM Peak Hour.....	5.16-15
5.16-11	Conventional Mitigation Measures – E. 59 th Street/E. 61 st Street Route.....	5.16-18
5.16-12	2008 Mitigated Build, Build, and No Build Conditions Comparison E. 59 th Street/E. 61 st Street Route Water Main Connection Study Area—AM Peak Hour	5.16-19
5.16-13	2008 Mitigated Build, Build, and No Build Conditions Comparison E. 59 th Street/E. 61 st Street Route Water Main Connection Study Area—PM Peak Hour	5.16-19

LIST OF FIGURES

5.1-1	Reasonable Worst-Case Water Main Connection Route, First Avenue Route.....	5.1-5
5.1-2	Representative Alternative Water Main Connection Route, Sutton Place Route.....	5.1-5
5.1-3	Representative Alternative Water Main Connection Route, E. 59 th Street/E. 61 st Street Route.....	5.1-6

TABLE OF CONTENTS

5.1-4	Representative Lane Closures, Construction of Water Mains	5.1-12
5.1-5	Potential Lane Closures for Water Main Connection Route, First Avenue.....	5.1-14
5.1-6	Potential Lane Closures for Water Main Construction on a Cross Street.....	5.1-14
5.1-7	Potential Lane Closures Required for Water Main Construction, Sutton Place Route.....	5.1-14
5.2-1	Land Use	5.2-1
5.2-2	Zoning	5.2-4
5.3-1	Public Open Spaces	5.3-1
5.5-1	Historic Resources.....	5.5-2
5.5-2	Architectural Resource	5.5-5
5.6-1	Visual Resources	5.6-1
5.6-2	Photographs of Study Area.....	5.6-1
5.6-3	Photographs of Study Area.....	5.6-1
5.6-4	Photographs of Study Area.....	5.6-2
5.6-5	Photographs of Study Area.....	5.6-2
5.6-6	Photographs of Study Area.....	5.6-2
5.6-7	Photographs of Study Area.....	5.6-2
5.6-8	Photographs of Study Area.....	5.6-2
5.6-9	Photographs of Study Area.....	5.6-3
5.6-10	Photographs of Study Area.....	5.6-3
5.6-11	Photographs of Study Area.....	5.6-3
5.6-12	Photographs of Study Area.....	5.6-3
5.6-13	Photographs of Study Area.....	5.6-3
5.9-1	2004 Existing Traffic Volume Network, Water Main Study Area, First Avenue Route— AM Peak Hour.....	5.9-1
5.9-2	2004 Existing Traffic Volume Network, Water Main Study Area, First Avenue Route— Midday Peak Hour.....	5.9-1
5.9-3	2004 Existing Traffic Volume Network, Water Main Study Area, First Avenue Route— PM Peak Hour	5.9-1
5.9-4	2004 Existing Traffic Volume Network, Water Main Study Area, Sutton Place Route— AM Peak Hour.....	5.9-7
5.9-5	2004 Existing Traffic Volume Network, Water Main Study Area, Sutton Place Route— Midday Peak Hour.....	5.9-7
5.9-6	2004 Existing Traffic Volume Network, Water Main Study Area, Sutton Place Route— PM Peak Hour	5.9-7
5.9-7	2004 Existing Traffic Volume Network, Water Main Study Area, AM Peak Hour.....	5.9-10
5.9-8	2004 Existing Traffic Volume Network, Water Main Study Area, E. 59 th Street/E. 61 st Street Route—Midday Peak Hour	5.9-10
5.9-9	2004 Existing Traffic Volume Network, Water Main Study Area, PM Peak Hour	5.9-10
5.9-10	2008 No Build Traffic Volume Network, Water Main Study Area, First Avenue Route— AM Peak Hour.....	5.9-13
5.9-11	2008 No Build Traffic Volume Network, Water Main Study Area, First Avenue Route— Midday Peak Hour.....	5.9-13
5.9-12	2008 No Build Traffic Volume Network, Water Main Study Area, First Avenue Route— PM Peak Hour	5.9-13

TABLE OF CONTENTS

5.9-13	2008 No Build Traffic Volume Network, Water Main Study Area, Sutton Place Route— AM Peak Hour	5.9-15
5.9-14	2008 No Build Traffic Volume Network, Water Main Study Area, Sutton Place Route— Midday Peak Hour	5.9-15
5.9-15	2008 No Build Traffic Volume Network, Water Main Study Area, Sutton Place Route— PM Peak Hour	5.9-15
5.9-16	2008 No Build Traffic Volume Network, Water Main Study Area, E. 59 th Street/E. 61 st Street Route—AM Peak Hour	5.9-15
5.9-17	2008 No Build Traffic Volume Network, Water Main Study Area, E. 59 th Street/E. 61 st Street Route—Midday Peak Hour	5.9-15
5.9-18	2008 No Build Traffic Volume Network, Water Main Study Area, E. 59 th Street/E. 61 st Street Route—PM Peak Hour	5.9-15
5.9-19	2008 Build Traffic Volume Network, Main Study Area, First Avenue Route—AM Peak Hour	5.9-19
5.9-20	2008 Build Traffic Volume Network, Water Main Study Area, First Avenue Route— Midday Peak Hour	5.9-19
5.9-21	2008 Build Traffic Volume Network, Main Study Area, First Avenue Route—PM Peak Hour	5.9-19
5.9-22	Roadway Configurations, First Avenue Route, Segment 1—AM Peak Hour	5.9-19
5.9-23	Roadway Configurations, First Avenue Route, Segment 1—Midday Peak Hour	5.9-19
5.9-24	Roadway Configurations, First Avenue Route, Segment 1—PM Peak Hour	5.9-19
5.9-25	Roadway Configurations, First Avenue Route, Segment 3—AM Peak Hour	5.9-19
5.9-26	Roadway Configurations, First Avenue Route, Segment 3—Midday Peak Hour	5.9-19
5.9-27	Roadway Configurations, First Avenue Route, Segment 3—PM Peak Hour	5.9-19
5.9-28	Roadway Configurations, First Avenue Route, Segment 5	5.9-19
5.9-29	Roadway Configurations, First Avenue Route, Segment 7	5.9-19
5.9-30	Roadway Configurations, First Avenue Route, Segment 9	5.9-19
5.9-31	Roadway Configurations, First Avenue Route, Segment 10	5.9-19
5.9-32	2008 Build Traffic Volume Network, Main Study Area, Sutton Place Route—AM Peak Hour	5.9-30
5.9-33	2008 Build Traffic Volume Network, Water Main Study Area, Sutton Place Route— Midday Peak Hour	5.9-30
5.9-34	2008 Build Traffic Volume Network, Main Study Area, Sutton Place Route—PM Peak Hour	5.9-30
5.9-35	Roadway Configurations, Sutton Place Route, E. 59 th Street Segment	5.9-30
5.9-36	Roadway Configurations, Sutton Place Route, Segment 1—AM Peak Hour	5.9-30
5.9-37	Roadway Configurations, Sutton Place Route, Segment 1—Midday Peak Hour	5.9-30
5.9-38	Roadway Configurations, Sutton Place Route, Segment 1—PM Peak Hour	5.9-30
5.9-39	Roadway Configurations, Sutton Place Route, Segment 3—AM Peak Hour	5.9-30
5.9-40	Roadway Configurations, Sutton Place Route, Segment 3—Midday Peak Hour	5.9-30
5.9-41	Roadway Configurations, Sutton Place Route, Segment 3—PM Peak Hour	5.9-30
5.9-42	Roadway Configurations, Sutton Place Route, Segment 5	5.9-30
5.9-43	Roadway Configurations, Sutton Place Route, Segment 9	5.9-30
5.9-44	2008 Build Traffic Volume Network, Water Main Study Area, E. 59 th Street/E. 61 st Street Route—AM Peak Hour	5.9-38
5.9-45	2008 Build Traffic Volume Network, Water Main Study Area, E. 59 th Street/E. 61 st Street Route—Midday Peak Hour	5.9-38

TABLE OF CONTENTS

5.9-46 2008 Build Traffic Volume Network, Water Main Study Area,
E. 59th Street/E. 61st Street Route—PM Peak Hour..... 5.9-38

5.9-47 Roadway Configurations, E. 59th Street/E. 61st Street Segment 1—AM Peak Hour..... 5.9-38

5.9-48 Roadway Configurations, E. 59th Street/E. 61st Street Segment 1—Midday Peak Hour..... 5.9-38

5.9-49 Roadway Configurations, E. 59th Street/E. 61st Street Segment 1—PM Peak Hour..... 5.9-38

5.9-50 Roadway Configurations, E. 59th Street/E. 61st Street Segment 3..... 5.9-38

5.9-51 Roadway Configurations, E. 59th Street/E. 61st Street Segment 5..... 5.9-38

5.9-52 Roadway Configurations, E. 59th Street/E. 61st Street Segment 6..... 5.9-38

5.9-53 Roadway Configurations, E. 59th Street/E. 61st Street Segment 8..... 5.9-38

5.10-1 2004 Existing Pedestrian Volumes Water Main Study Area—Scenario A..... 5.10-4

5.11-1 Total Predicted 24-Hour PM_{2.5} Concentrations for Water Main Construction
Reasonable Worst-Case Route Base Scenario..... 5.11-12

5.11-2 Total Predicted 24-Hour PM_{2.5} Concentrations for Water Main Construction
Reasonable Worst-Case Route Scenario A..... 5.11-14

5.12-1 Water Main Connection Noise Survey Locations..... 5.12-2

5.12-2 First Avenue Route Receptor Locations—Without Venuri Chambers..... 5.12-5

5.12-3 First Avenue Route Cross Street Receptor Locations..... 5.12-5

5.12-4 First Avenue Route Receptor Locations—With Venuri Chambers..... 5.12-5

5.12-5 Sutton Place Receptor Locations—Without Venuri Chambers..... 5.12-5

5.12-6 E. 59th Street/E. 61st Street Route Cross Street Receptor Locations..... 5.12-5

5.16-1 First Avenue Route Base Scenario—Segment 1 2004 Existing and 2008
Roadway Configurations Water Main Study Area—AM Peak Hour..... 5.16-2

5.16-2 First Avenue Route Base Scenario—Segment 1 2004 Existing and 2008
Roadway Configurations Water Main Study Area—Midday Peak Hour..... 5.16-2

5.16-3 First Avenue Route Base Scenario—Segment 3 2004 Existing and 2008
Roadway Configurations Water Main Study Area—AM Peak Hour..... 5.16-3

5.16-4 First Avenue Route Base Scenario—Segment 3 2004 Existing and 2008
Roadway Configurations Water Main Study Area—Midday Peak Hour..... 5.16-3

5.16-5 First Avenue Route Base Scenario Segment 7—2004 Existing and
2008 Roadway Configurations..... 5.16-3

5.16-6 Traffic Diversion Estimates—First Avenue Route, AM Peak Hour..... 5.16-8

5.16-7 Traffic Diversion Estimates—First Avenue Route, Midday Peak Hour..... 5.16-8

5.16-8 Traffic Diversion Estimates—First Avenue Route, PM Peak Hour..... 5.16-8

5.16-9 2008 Build Traffic Volume With Diversion—First Avenue Route, AM Peak Hour..... 5.16-8

5.16-10 2008 Build Traffic Volume With Diversion—First Avenue Route, Midday Peak Hour..... 5.16-8

5.16-11 2008 Build Traffic Volume With Diversion Estimates—First Avenue Route, PM Peak Hour..... 5.16-8

CHAPTER 6: EAST 59TH STREET/SECOND AVENUE SHAFT SITE

6.1 Project Description..... 6.1-1

6.1.1 Introduction..... 6.1-1

6.1.2 Description of E. 59th Street/Second Avenue Shaft Site..... 6.1-1

6.1.3 Location of Shaft Components on the E. 59th Street/Second Avenue Shaft Site..... 6.1-2

6.1.4 Description of Construction at the E. 59th Street/Second Avenue Shaft Site..... 6.1-4

TABLE OF CONTENTS

Construction Activity	6.1-4
Construction Equipment.....	6.1-7
Water Main Construction	6.1-7
Construction Schedule.....	6.1-9
6.1.5 Activation and Operation	6.1-10
6.1.6 Permits and Approvals	6.1-11
6.2 Land Use and Community Facilities, Zoning, and Public Policy.....	6.2-1
6.2.1 Introduction.....	6.2-1
6.2.2 Existing Conditions	6.2-1
Land Use	6.2-1
Community Facilities	6.2-2
Zoning and Public Policy	6.2-3
6.2.3 Future Conditions Without the Project.....	6.2-4
Land Use and Community Facilities	6.2-4
Zoning and Public Policy	6.2-4
6.2.4 Future Conditions With the Project.....	6.2-5
Construction	6.2-5
Activation and Operation	6.2-9
6.3 Open Space	6.3-1
6.3.1 Introduction.....	6.3-1
6.3.2 Existing Conditions	6.3-1
6.3.3 Future Conditions Without the Project.....	6.3-2
6.3.4 Future Conditions With the Project.....	6.3-3
Construction	6.3-3
Operation.....	6.3-5
6.4 Socioeconomic Conditions.....	6.4-1
6.4.1 Introduction.....	6.4-1
6.4.2 Existing Conditions	6.4-2
Residents and Businesses in the Vicinity of the E. 59 th Street/Second Avenue Shaft Site	6.4-2
Water and Sewer Rates.....	6.4-2
6.4.3 Future Conditions Without the Project.....	6.4-2
Residents and Businesses in the Vicinity of the E. 59 th Street/Second Avenue Shaft Site	6.4-2
Water and Sewer Rates.....	6.4-3
6.4.4 Future Conditions with the Project.....	6.4-3
Residents and Businesses in the Vicinity of the E. 59 th Street/Second Avenue Shaft Site	6.4-3
Water and Sewer Rates.....	6.4-4
Conclusions	6.4-5
6.5 Historic Resources	6.5-1
6.5.1 Introduction.....	6.5-1
6.5.2 Existing Conditions	6.5-1
Archaeological Resources	6.5-1

TABLE OF CONTENTS

Architectural Resources..... 6.5-2

6.5.3 Future Conditions Without the Project..... 6.5-3

 Archaeological Resources 6.5-3

 Architectural Resources..... 6.5-3

6.5.4 Future Conditions with the Project..... 6.5-3

 Construction 6.5-3

 Operation 6.5-5

6.6 Urban Design and Visual Resources6.6-1

6.6.1 Introduction 6.6-1

6.6.2 Existing Conditions 6.6-1

 Urban Design..... 6.6-1

 Visual Resources 6.6-2

6.6.3 Future Conditions Without the Project..... 6.6-3

 Urban Design..... 6.6-3

 Visual Resources 6.6-3

6.6.4 Future Conditions With the Project 6.6-4

 Construction 6.6-4

 Operation 6.6-7

6.7 Neighborhood Character.....6.7-1

6.7.1 Introduction 6.7-1

6.7.2 Existing Conditions 6.7-1

 Alternative Shaft Site..... 6.7-1

 Study Area..... 6.7-1

6.7.3 Future Conditions Without the Project..... 6.7-3

6.7.4 Future Conditions With the Project 6.7-4

 Construction 6.7-4

 Operation 6.7-6

6.8 Infrastructure and Energy6.8-1

6.8.1 Introduction 6.8-1

6.8.2 Existing Conditions 6.8-1

6.8.3 Future Conditions Without the Project..... 6.8-1

6.8.4 Future Conditions With the Project 6.8-2

 Construction 6.8-2

 Activation and Operation..... 6.8-4

6.9 Traffic and Parking.....6.9-1

6.9.1 Introduction 6.9-1

6.9.2 Shaft Site Construction Traffic Conditions..... 6.9-1

6.9.3 Water Main Construction Traffic Conditions 6.9-6

6.9.4 Conclusions 6.9-7

6.10 Transit and Pedestrians6.10-1

6.10.1 Introduction 6.10-1

TABLE OF CONTENTS

6.10.2	Shaft Site Construction Transit and Pedestrian Conditions	6.10-1
6.10.3	Water Main Connection Construction Transit and Pedestrian Conditions	6.10-2
6.10.4	Conclusions	6.10-3
6.11	Air Quality	6.11-1
6.11.1	Introduction	6.11-1
6.11.2	Existing Conditions	6.11-1
6.11.3	Future Conditions Without the Project	6.11-1
6.11.4	Future Conditions With the Project	6.11-2
	Construction	6.11-2
	Operation	6.11-7
6.12	Noise	6.12-1
6.12.1	Introduction	6.12-1
6.12.2	Existing Conditions	6.12-1
	Monitoring Locations	6.12-1
	Monitoring Results	6.12-2
6.12.3	Future Conditions Without the Project	6.12-2
6.12.4	Future Conditions With the Project	6.12-3
	Construction	6.12-3
	Operation	6.12-11
6.13	Vibration	6.13-1
6.13.1	Introduction	6.13-1
6.13.2	Existing Conditions	6.13-1
6.13.3	Future Conditions Without the Project	6.13-1
6.13.4	Future Conditions with the Project	6.13-2
	Construction	6.13-2
	Operation	6.13-5
6.14	Hazardous Materials	6.14-1
6.14.1	Introduction	6.14-1
6.14.2	Existing Conditions	6.14-1
	Current Site Conditions	6.14-1
	Adjacent and Vicinity Land Uses	6.14-2
	Geology and Hydrogeology	6.14-2
	Records Search	6.14-2
	Historical Uses of the Shaft Site and Adjacent Properties	6.14-4
6.14.3	Future Conditions Without the Project	6.14-5
6.14.4	Future Conditions With the Project	6.14-5
	Activation and Operation	6.14-6
6.15	Public Health	6.15-1
6.15.1	Introduction	6.15-1
6.15.2	Existing Conditions	6.15-1
6.15.3	Future Conditions Without the Project	6.15-1

TABLE OF CONTENTS

6.15.4 Future Conditions With the Project 6.15-2
 Construction 6.15-2
 Activation and Operation 6.15-5
6.16 Mitigation Measures.....6.16-1
 6.16.1 Introduction 6.16-1
 6.16.2 Traffic 6.16-1
 6.16.3 Air Quality 6.16-1
 6.16.4 Noise..... 6.16-2
6.17 Unavoidable Adverse Impacts.....6.17-1

LIST OF TABLES

6.1-1 E. 59th Street/Second Avenue Shaft Site Average Equipment Usage Assumptions for Construction With Raise Bore Excavation..... 6.1-8
6.1-2 E. 59th Street/Second Avenue Shaft Site Average Equipment Usage Assumptions for Construction With Surface Excavation 6.1-8
6.1-3 Shaft Construction Stages at E. 59th Street/Second Avenue Shaft Site Raise Bore vs. Surface Excavation 6.1-10
6.2-1 Zoning Districts in the Study Area 6.2-4
6.3-3 Open Spaces in the 400-Foot Study Area 6.3-1
6.5-1 Architectural Resources Within the E. 59th Street/Second Avenue Shaft Site Study Area 6.5-3
6.8-1 Utility Lines Located on E. 59th Street Between First and Second Avenues 6.8-1
6.11-1 On-Site Construction Equipment (Raise Bore Method) for Peak Short Term and Annual Period 6.11-4
6.11-2 Construction Equipment Data (Raise Bore Method) 6.11-5
6.11-3 Results of Dispersion Analysis for Raise Bore Method Construction Activities 6.11-6
6.12-1 Baseline Ambient Noise Monitoring Results for the E. 59th Street/Second Avenue Shaft Site..... 6.12-2
6.12-2 Identification and Description of Selected Shaft Receptor Locations 6.12-4
6.12-3 Noise Levels - Average Workday 6.12-6
6.12-4 Noise Levels - Peak Hour 6.12-7
6.13-1 Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Shaft Site Construction 6.13-4
6.16-1 Comparison of Noise Levels With and Without 15 dBA Acoustical Enclosure 6.16-4

LIST OF FIGURES

6.1-1 Site Location..... 6.1-1
6.1-2 Conceptual Site Layout 6.1-2
6.1-3 Temporary Roadway Detours..... 6.1-9
6.2-1 Land Use 6.2-2
6.2-2 Zoning 6.2-3
6.3-1 Public Open Spaces 6.3-1
6.5-1 Historic Resources..... 6.5-1
6.6-1 Visual Resources 6.6-1
6.6-2 Photographs of Study Area..... 6.6-1

TABLE OF CONTENTS

6.6-3	Photographs of Study Area	6.6-1
6.6-4	Photographs of Study Area	6.6-2
6.6-5	Photographs of Study Area	6.6-3
6.6-6	Photographs of Study Area	6.6-4
6.11-1	Predicted PM _{2.5} 24-Hour Concentrations for Construction Activities.....	6.11-3
6.12-1	Noise Monitoring Locations.....	6.12-1
6.12-2	Noise Receptor Locations	6.12-3

CHAPTER 7: EAST 61ST STREET SHAFT SITE

7.1	Project Description	7.1-1
7.1.1	Introduction	7.1-1
7.1.2	Description of E. 61 st Street Shaft Site	7.1-1
7.1.3	Location of Shaft Components on the E. 61 st Street Shaft Site	7.1-2
7.1.4	Description of Construction at the E. 61 st Street Shaft Site.....	7.1-4
	Construction Activity	7.1-4
	Construction Equipment.....	7.1-6
	Water Main Construction	7.1-8
	Construction Schedule.....	7.1-9
7.1.5	Activation and Operation	7.1-9
7.1.6	Permits and Approvals	7.1-10
7.2	Land Use and Community Facilities, Zoning, and Public Policy.....	7.2-1
7.2.1	Introduction	7.2-1
7.2.2	Existing Conditions	7.2-1
	Land Use	7.2-1
	Community Facilities	7.2-3
	Zoning and Public Policy	7.2-3
7.2.3	Future Conditions Without the Project.....	7.2-5
	Land Use and Community Facilities	7.2-5
	Zoning and Public Policy	7.2-5
7.2.4	Future Conditions With the Project.....	7.2-6
	Construction	7.2-6
	Activation and Operation	7.2-10
7.3	Open Space	7.3-1
7.3.1	Introduction	7.3-1
7.3.2	Existing Conditions	7.3-1
7.3.3	Future Conditions Without the Project.....	7.3-2
7.3.4	Future Conditions With the Project.....	7.3-2
	Construction	7.3-2
	Operation.....	7.3-3
7.4	Socioeconomic Conditions.....	7.4-1
7.4.1	Introduction	7.4-1

TABLE OF CONTENTS

7.4.2	Existing Conditions	7.4-2
	Residents and Businesses in the Vicinity of the E. 61 st Street Shaft Site.....	7.4-2
	Water and Sewer Rates	7.4-2
7.4.3	Future Conditions Without the Project	7.4-2
	Residents and Businesses in the Vicinity of the E. 61 st Street Shaft Site.....	7.4-2
	Water and Sewer Rates.....	7.4-3
7.4.4	Future Conditions With the Project	7.4-3
	Residents and Businesses in the Vicinity of the E. 61 st Street Shaft Site.....	7.4-3
	Water and Sewer Rates.....	7.4-4
	Conclusions	7.4-6
7.5	Historic Resources	7.5-1
7.5.1	Introduction	7.5-1
7.5.2	Existing Conditions	7.5-1
	Archaeological Resources	7.5-1
	Architectural Resources.....	7.5-2
7.5.3	Future Conditions Without the Project	7.5-3
	Archaeological Resources	7.5-3
	Architectural Resources.....	7.5-3
7.5.4	Future Conditions With the Project	7.5-4
	Construction	7.5-4
	Operation	7.5-6
7.6	Urban Design and Visual Resources	7.6-1
7.6.1	Introduction	7.6-1
7.6.2	Existing Conditions	7.6-1
	Urban Design.....	7.6-1
	Visual Resources	7.6-2
7.6.3	Future Conditions Without the Project	7.6-2
	Urban Design.....	7.6-2
	Visual Resources	7.6-3
7.6.4	Future Conditions With the Project	7.6-3
	Construction	7.6-3
	Operation	7.6-6
7.7	Neighborhood Character.....	7.7-1
7.7.1	Introduction	7.7-1
7.7.2	Existing Conditions	7.7-1
	Alternative Shaft Site.....	7.7-1
	Study Area.....	7.7-1
7.7.3	Future Conditions Without the Project	7.7-3
7.7.4	Future Conditions With the Project	7.7-4
	Construction	7.7-4
	Operation	7.7-5

TABLE OF CONTENTS

7.8 Infrastructure and Energy	7.8-1
7.8.1 Introduction.....	7.8-1
7.8.2 Existing Conditions.....	7.8-1
7.8.3 Future Conditions Without the Project.....	7.8-1
7.8.4 Future Conditions With the Project.....	7.8-2
Construction.....	7.8-2
Activation and Operation.....	7.8-4
7.9 Traffic and Parking	7.9-1
7.9.1 Introduction.....	7.9-1
7.9.2 Shaft Site Construction Traffic Conditions.....	7.9-1
7.9.3 Water Main Construction Traffic Conditions.....	7.9-5
7.9.4 Conclusions.....	7.9-6
7.10 Transit and Pedestrians	7.10-1
7.10.1 Introduction.....	7.10-1
7.10.2 Shaft Site Construction Transit and Pedestrian Conditions.....	7.10-1
7.10.3 Water Main Construction Transit and Pedestrian Conditions.....	7.10-2
7.10.4 Conclusions.....	7.10-3
7.11 Air Quality	7.11-1
7.11.1 Introduction.....	7.11-1
7.11.2 Existing Conditions.....	7.11-1
7.11.3 Future Conditions Without the Project.....	7.11-1
7.11.4 Future Conditions With the Project.....	7.11-2
Construction.....	7.11-2
Operation.....	7.11-8
7.12 Noise	7.12-1
7.12.1 Introduction.....	7.12-1
7.12.2 Existing Conditions.....	7.12-1
Monitoring Locations.....	7.12-1
Monitoring Results.....	7.12-2
7.12.3 Future Conditions Without the Project.....	7.12-2
7.12.4 Future Conditions With the Project.....	7.12-3
Construction.....	7.12-3
Activation and Operation.....	7.12-13
7.13 Vibration	7.13-1
7.13.1 Introduction.....	7.13-1
7.13.2 Existing Conditions.....	7.13-1
7.13.3 Future Conditions Without the Project.....	7.13-2
7.13.4 Future Conditions With the Project.....	7.13-2
Construction.....	7.13-2
Operation.....	7.13-5

TABLE OF CONTENTS

7.14 Hazardous Materials.....7.14-1

7.14.1 Introduction 7.14-1

7.14.2 Existing Conditions 7.14-1

 Current Site Conditions 7.14-1

 Adjacent and Vicinity Land Uses 7.14-2

 Geology and Hydrogeology..... 7.14-2

 Records Search 7.14-2

 Historical Uses of the Shaft Site and Adjacent Properties..... 7.14-4

7.14.3 Future Conditions Without the Project 7.14-5

7.14.4 Future Conditions With the Project 7.14-5

 Activation and Operation..... 7.14-6

7.15 Public Health7.15-1

7.15.1 Introduction 7.15-1

7.15.2 Existing Conditions 7.15-1

7.15.3 Future Conditions Without the Project 7.15-1

7.15.4 Future Conditions With the Project 7.15-2

 Construction 7.15-2

 Activation and Operation..... 7.15-5

7.16 Mitigation Measures.....7.16-1

7.16.1 Introduction 7.16-1

7.16.2 Land Use and Community Facilities, Zoning, and Public Policy 7.16-1

7.16.3 Traffic 7.16-1

7.16.4 Air Quality 7.16-2

7.16.5 Noise..... 7.16-2

7.17 Unavoidable Adverse Impacts.....7.17-1

LIST OF TABLES

7.1-1 E. 61st Street Shaft Site Average Equipment Usage Assumptions for Construction With Raise Bore Excavation 7.1-7

7.1-2 E. 61st Street Shaft Site Average Equipment Usage Assumptions for Construction With Surface Excavation..... 7.1-8

7.1-3 Shaft Construction Stages at E. 61st Street Shaft Site Raise Bore vs. Surface Excavation..... 7.1-9

7.2-1 Community Facilities in the Study Area 7.2-3

7.2-2 Zoning Districts in the Study Area 7.2-4

7.3-1 Open Spaces in the 400-Foot Study Area..... 7.3-1

7.5-1 Architectural Resources Within the E. 61st Street Shaft Site Study Area..... 7.5-3

7.8-1 Utility Lines Located on East 61st Street Between First and Second Avenues..... 7.8-1

7.11-1 On-Site Construction Equipment (Raise Bore Method) for Peak Short Term and Annual Period..... 7.11-4

7.11-2 Construction Equipment Data (Raise Bore Method)..... 7.11-5

7.11-3 Results of Dispersion Analysis for Raise Bore Method Construction Activities 7.11-6

7.12-1 Baseline Ambient Noise Monitoring Results for the E. 61st Street Shaft Site..... 7.12-2

TABLE OF CONTENTS

7.12-2 Identification and Description of Selected Shaft Receptor Locations 7.12-4

7.12-3 Noise Levels—Average Workday..... 7.12-6

7.12-4 Noise Levels—Peak Hour..... 7.12-7

7.13-1 Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Shaft Site Construction 7.13-4

7.16-1 Comparison of Noise Levels With and Without 15 dBA Acoustical Enclosure 7.16-5

LIST OF FIGURES

7.1-1 Site Locations.....7.1-1

7.1-2 Conceptual Site Layout7.1-2

7.2-1 Land Use7.2-2

7.2-2 Zoning7.2-4

7.3-1 Public Open Spaces.....7.3-1

7.5-1 Historic Resources7.5-2

7.6-1 Visual Resources.....7.6-1

7.6-2 Photographs of Study Area7.6-1

7.6-3 Photographs of Study Area7.6-1

7.6-4 Photographs of Study Area7.6-2

7.6-5 Photographs of Study Area7.6-2

7.11-1 Predicted PM_{2.5} 24-Hour Concentrations for Construction Activities.....7.11-3

7.12-1 Noise Monitoring Locations.....7.12-1

7.12-2 Noise Receptor Locations7.12-3

CHAPTER 8: EAST 54TH STREET/SECOND AVENUE SHAFT SITE

8.1 Project Description.....8.1-1

8.1.1 Introduction 8.1-1

8.1.2 Description of E. 54th Street/Second Avenue Shaft Site..... 8.1-1

8.1.3 Location of Shaft Components on the E. 54th Street/Second Avenue Shaft Site 8.1-2

8.1.4 Description of Construction at the E. 54th Street/Second Avenue Shaft Site..... 8.1-3

Construction Activity 8.1-3

Construction Equipment..... 8.1-7

Water Main Construction 8.1-9

Construction Schedule..... 8.1-9

8.1.5 Activation and Operation 8.1-10

8.1.6 Permits and Approvals 8.1-10

8.2 Land Use and Community Facilities, Zoning, and Public Policy.....8.2-1

8.2.1 Introduction 8.2-1

8.2.2 Existing Conditions 8.2-1

Land Use 8.2-1

Community Facilities 8.2-3

Zoning and Public Policy 8.2-3

8.2.3 Future Conditions Without the Project..... 8.2-5

TABLE OF CONTENTS

Land Use and Community Facilities 8.2-5

Zoning and Public Policy 8.2-6

8.2.4 Future Conditions With the Project 8.2-6

 Construction 8.2-6

 Activation and Operation..... 8.2-11

8.3 Open Space.....8.3-1

8.3.1 Introduction 8.3-1

8.3.2 Existing Conditions 8.3-1

8.3.3 Future Conditions Without the Project 8.3-2

8.3.4 Future Conditions With the Project 8.3-2

 Construction 8.3-2

 Activation and Operation..... 8.3-4

8.4 Socioeconomic Conditions.....8.4-1

8.4.1 Introduction 8.4-1

8.4.2 Existing Conditions 8.4-2

 Residents and Businesses in the Vicinity of the E. 54th Street/Second Avenue Shaft Site..... 8.4-2

 Water and Sewer Rates 8.4-2

8.4.3 Future Conditions Without the Project 8.4-3

 Residents and Businesses in the Vicinity of the E. 54th Street/Second Avenue Shaft Site..... 8.4-3

 Water and Sewer Rates..... 8.4-3

8.4.4 Future Conditions with the Project 8.4-3

 Residents and Businesses in the Vicinity of the E. 54th Street/Second Avenue Shaft Site..... 8.4-3

 Water and Sewer Rates..... 8.4-5

 Conclusions 8.4-7

8.5 Historic Resources8.5-1

8.5.1 Introduction 8.5-1

8.5.2 Existing Conditions 8.5-1

 Archaeological Resources 8.5-1

 Architectural Resources..... 8.5-3

8.5.3 Future Conditions Without the Project 8.5-4

 Archaeological Resources 8.5-4

 Architectural Resources..... 8.5-4

8.5.4 Future Conditions With the Project 8.5-5

 Construction 8.5-5

 Operation 8.5-7

8.6 Urban Design and Visual Resources8.6-1

8.6.1 Introduction 8.6-1

8.6.2 Existing Conditions 8.6-1

 Urban Design..... 8.6-1

 Visual Resources 8.6-2

8.6.3 Future Conditions Without the Project 8.6-3

TABLE OF CONTENTS

Urban Design.....	8.6-3
Visual Resources	8.6-3
8.6.4 Future Conditions With the Project.....	8.6-4
Construction	8.6-4
Operation.....	8.6-7
8.7 Neighborhood Character	8.7-1
8.7.1 Introduction	8.7-1
8.7.2 Existing Conditions	8.7-1
Alternative Shaft Site	8.7-1
Study Area.....	8.7-1
8.7.3 Future Conditions Without the Project.....	8.7-3
8.7.4 Future Conditions With the Project.....	8.7-4
Construction	8.7-4
Operation.....	8.7-6
8.8 Infrastructure and Energy	8.8-1
8.8.1 Introduction	8.8-1
8.8.2 Existing Conditions	8.8-1
8.8.3 Future Conditions Without the Project.....	8.8-1
8.8.4 Future Conditions With the Project.....	8.8-2
Construction	8.8-2
Activation and Operation	8.8-4
8.9 Traffic and Parking.....	8.9-1
8.9.1 Introduction	8.9-1
8.9.2 Shaft Site Construction Traffic Conditions	8.9-1
Traffic Operations Analysis	8.9-5
8.9.3 Water Main Connection Construction Traffic Conditions	8.9-7
8.9.4 Conclusions	8.9-9
8.10 Transit and Pedestrians	8.10-1
8.10.1 Introduction	8.10-1
8.10.2 Shaft Site Construction Transit and Pedestrian Conditions.....	8.10-1
Pedestrian Operations Analysis.....	8.10-2
8.10.3 Water Main Connection Construction Transit and Pedestrian Conditions.....	8.10-6
8.10.4 Conclusions	8.10-7
8.11 Air Quality	8.11-1
8.11.1 Introduction	8.11-1
8.11.2 Existing Conditions	8.11-1
8.11.3 Future Conditions Without the Project.....	8.11-1
8.11.4 Future Conditions With the Project.....	8.11-2
Construction	8.11-2
Operation.....	8.11-7

TABLE OF CONTENTS

8.12 Noise	8.12-1
8.12.1 Introduction	8.12-1
8.12.2 Existing Conditions	8.12-1
Monitoring Locations	8.12-1
Monitoring Results	8.12-2
8.12.3 8.12.3 Future Conditions Without the Project	8.12-3
8.12.4 8.12.4 Future Conditions with the Project	8.12-3
Construction	8.12-3
Activation and Operation.....	8.12-16
8.13 Vibration	8.13-1
8.13.1 Introduction	8.13-1
8.13.2 Existing Conditions	8.13-1
8.13.3 Future Conditions Without the Project	8.13-1
8.13.4 Future Conditions with the Project	8.13-2
Construction	8.13-2
Operation	8.13-5
8.14 Hazardous Materials	8.14-1
8.14.1 Introduction	8.14-1
8.14.2 Existing Conditions	8.14-1
Current Site Conditions	8.14-1
Adjacent and Vicinity Land Uses	8.14-2
Geology and Hydrogeology.....	8.14-2
Records Search	8.14-2
Historical Uses of the Shaft Site and Adjacent Properties	8.14-4
8.14.3 Future Conditions Without the Project	8.14-5
8.14.4 Future Conditions With the Project	8.14-5
Activation and Operation.....	8.14-6
8.15 Public Health	8.15-1
8.15.1 Introduction	8.15-1
8.15.2 Existing Conditions	8.15-1
8.15.3 Future Conditions Without the Project	8.15-1
8.15.4 Future Conditions With the Project	8.15-2
Construction	8.15-2
Activation and Operation.....	8.15-5
8.16 Mitigation Measures	8.16-1
8.16.1 Introduction	8.16-1
8.16.2 Open Space	8.16-1
8.16.3 Traffic and Parking	8.16-1
8.16.4 Air Quality	8.16-2
8.16.5 Noise.....	8.16-2
8.17 Unavoidable Adverse Impacts	8.17-1

TABLE OF CONTENTS

LIST OF TABLES

8.1-1	E. 54 th Street/Second Avenue Shaft Site Average Equipment Usage Assumptions for Construction With Raise Bore Excavation	8.1-8
8.1-2	E. 54 th Street/Second Avenue Shaft Site Average Equipment Usage Assumptions for Construction With Surface Excavation.....	8.1-8
8.1-3	Shaft Construction Stages at E. 54 th Street/Second Avenue Shaft Site Raise Bore vs. Surface Excavation.....	8.1-10
8.2-1	Community Facilities in the Study Area	8.2-3
8.2-2	Zoning Districts in the Study Area.....	8.2-4
8.3-1	Open Spaces in the 400-Foot Study Area	8.3-1
8.5-1	Architectural Resources Within the E. 54 th Street/Second Avenue Shaft Site Study Area	8.5-3
8.8-1	Utility Lines Located on East 54 th Street Between First and Second Avenues	8.8-1
8.9-1	2004 Existing Conditions—E. 54 th Street/Second Avenue Shaft Site Study Area.....	8.9-6
8.9-2	2008 No Build and 2004 Existing Conditions Comparison—E. 54 th Street/Second Avenue Shaft Site Study Area	8.9-8
8.9-3	2008 Build and No Build Conditions Comparison—E. 54 th Street/Second Avenue Shaft Site Study Area.....	8.9-8
8.10-1	2004 Existing Conditions: Pedestrian LOS Analysis for Sidewalks	8.10-3
8.10-2	2004 Existing Conditions: Pedestrian LOS Analysis for Corner Reservoirs	8.10-3
8.10-3	2004 Existing Conditions: Pedestrian LOS Analysis for Crosswalks	8.10-3
8.10-4	2008 No Build Conditions: Pedestrian LOS Analysis for Sidewalks.....	8.10-4
8.10-5	2008 No Build Conditions: Pedestrian LOS Analysis for Corner Reservoirs	8.10-4
8.10-6	2008 No Build Conditions: Pedestrian LOS Analysis for Crosswalks.....	8.10-4
8.10-7	2008 Build Conditions: Pedestrian LOS Analysis for Sidewalks	8.10-5
8.10-8	2008 Build Conditions: Pedestrian LOS Analysis for Corner Reservoirs.....	8.10-5
8.10-9	2008 Build Conditions: Pedestrian LOS Analysis for Crosswalks	8.10-6
8.11-1	On-Site Construction Equipment (Raise Bore Method) for Peak Short Term and Annual Period.....	8.11-4
8.11-2	Construction Equipment Data (Raise Bore Method).....	8.11-5
8.11-3	Results of Dispersion Analysis for Raise Bore Method Construction Activities	8.11-6
8.12-1	Baseline Ambient Noise Monitoring Results for the E. 54 th Street/Second Avenue Shaft Site	8.12-2
8.12-2	Identification and Description of Selected Shaft Receptor Locations	8.12-4
8.12-3	Noise Levels—Average Workday.....	8.12-7
8.12-4	Noise Levels—Peak Hour.....	8.12-9
8.13-1	Typical Levels of Vibration for Construction Equipment Similar to that Proposed for Shaft Site Construction	8.13-4
8.16-1	Comparison of Noise Levels With and Without 15 dBA Acoustical Enclosure	8.16-5

LIST OF FIGURES

8.1-1	Site Location	8.1-1
8.1-2	Conceptual Site Layout.....	8.1-2
8.2-1	Land Use	8.2-1
8.2-2	Zoning	8.2-3

TABLE OF CONTENTS

8.3-1	Public Open Spaces	8.3-1
8.5-1	Historic Resources.....	8.5-1
8.6-1	Visual Resources	8.6-1
8.6-2	Photographs of Study Area.....	8.6-1
8.6-3	Photographs of Study Area.....	8.6-2
8.6-4	Photographs of Study Area.....	8.6-2
8.6-5	Photographs of Study Area.....	8.6-2
8.6-6	Photographs of Study Area.....	8.6-2
8.6-7	Photographs of Study Area.....	8.6-4
8.9-1	2004 Existing Traffic Volumes, Shaft 33B Second Avenue and East 54 th Street Alternative.....	8.9-5
8.9-2	2008 No Build Traffic Volumes, Shaft 33B Second Avenue and East 54 th Street Alternative	8.9-6
8.9-3	2008 Build Traffic Volumes, Shaft 33B Second Avenue and East 54 th Street Alternative	8.9-7
8.10-1	2004 Existing Pedestrian Volumes, Shaft 33B Second Avenue and East 54 th Street Alternative	8.10-2
8.11-1	Predicted PM _{2.5} 24-Hour Concentrations for Construction Activities	8.11-3
8.12-1	Noise Monitoring Locations.....	8.12-1
8.12-2	Noise Receptor Locations.....	8.12-4

CHAPTER 9: WATER MAIN ONLY ALTERNATIVE

9.1	Description of the Water Main Only Alternative.....	9-1
9.1.1	Introduction	9-1
9.1.2	Conceptual Route	9-1
9.1.3	Construction	9-2
	Construction Method	9-2
	Construction Schedule	9-2
	Construction Costs.....	9-2
9.2	Evaluation of the Water Main Only Alternative.....	9-2
9.2.1	Consistency with Objectives.....	9-2
9.2.2	Probable Impacts of the Water Main Only Alternative	9-3
	Land Use and Community Facilities, Zoning, and Public Policy	9-3
	Open Space.....	9-5
	Socioeconomic Conditions	9-5
	Historic Resources.....	9-6
	Urban Design and Visual Resources	9-8
	Neighborhood Character.....	9-9
	Infrastructure and Energy	9-10
	Traffic and Parking.....	9-11
	Transit and Pedestrians.....	9-15
	Air Quality.....	9-15
	Noise.....	9-15
	Vibration.....	9-16
	Hazardous Materials.....	9-16

TABLE OF CONTENTS

Public Health 9-17
Mitigation Measures 9-17
Unavoidable Adverse Impacts 9-17

LIST OF TABLES

9.2-1 2008 Build and No Build Conditions—Water Main Only Alternative Study Area 9-14

LIST OF FIGURES

9.1-1 Potential Water Main Only Route9.1-1
9.2-1 Land Use for Potential Route9.2-3
9.2-2 2004 Existing Traffic Volumes Water Main Alternative9.2-12
9.2-3 2008 No Build Traffic Volumes Water Main Alternative.....9.2-12
9.2-4 2008 Build Traffic Volumes Water Main Alternative.....9.2-12

CHAPTER 10: NO ACTION ALTERNATIVE

10.1 Introduction..... 10-1
10.2 Evaluation of the No Action Alternative..... 10-1
10.2.1 Introduction 10-1
10.2.2 Land Use and Community Facilities, Zoning, and Public Policy 10-1
10.2.3 Open Space..... 10-2
10.2.4 Socioeconomic Conditions 10-2
10.2.5 Historic Resources..... 10-2
10.2.6 Urban Design and Visual Resources 10-2
10.2.7 Neighborhood Character 10-2
10.2.8 Infrastructure and Energy 10-3
10.2.9 Traffic and Parking..... 10-3
10.2.10 Transit and Pedestrians..... 10-3
10.2.11 Air Quality 10-3
10.2.12 Noise 10-3
10.2.13 Vibration 10-4
10.2.14 Hazardous Materials..... 10-4
10.2.15 Public Health 10-4

CHAPTER 11: COMPARISON OF ALTERNATIVES

11.1 Introduction..... 11-1
11.2 Characteristics and Engineering Issues 11-1
11.2.1 Shaft Sites..... 11-1
Preferred Shaft Site 11-2
E. 59th Street/Second Avenue Shaft Site 11-4
E. 61st Street Shaft Site..... 11-4

TABLE OF CONTENTS

E. 54 th Street/Second Avenue Shaft Site.....	11-5
11.2.2 Duration of Construction for Water Main Connection Routes	11-5
11.3 Comparison of Environmental Impacts	11-6
11.3.1 Overview	11-6
11.3.2 Land Use and Community Facilities, Zoning, and Public Policy	11-8
Shaft Sites	11-8
Water Main Connections	11-10
11.3.3 Open Space.....	11-10
Shaft Sites	11-10
Water Main Connections	11-11
11.3.4 Socioeconomic Conditions	11-12
Shaft Sites	11-12
Water Main Connections	11-14
11.3.5 Historic Resources	11-14
Shaft Sites	11-14
Water Main Connections	11-15
11.3.6 Urban Design and Visual Resources	11-16
Shaft Sites	11-16
Water Main Connections	11-16
11.3.7 Neighborhood Character.....	11-18
Shaft Sites	11-18
Water Main Connections	11-18
11.3.8 Infrastructure and Energy	11-18
11.3.9 Traffic & Parking.....	11-19
Shaft Sites	11-19
Water Main Connections	11-20
11.3.10 Transit & Pedestrians.....	11-23
Shaft Sites	11-23
Water Main Connections	11-23
11.3.11 Air Quality	11-23
Shaft Sites	11-23
Water Main Connections	11-24
11.3.12 Noise	11-24
Shaft Sites	11-24
Water Main Connections	11-26
11.3.13 Vibration.....	11-27
11.3.14 Hazardous Materials	11-27
11.3.15 Public Health	11-28
11.4 Water Main Only Alternative.....	11-28
11.4.1 Overview	11-28
11.4.2 Urban Design and Visual Resources	11-28

TABLE OF CONTENTS

11.4.3 Traffic..... 11-29
11.4.4 Noise 11-29

LIST OF TABLES

11.2-1 Site Characteristics and Engineering Issues 11-3
11.2-2 Estimated Months of Construction, Water Main Connection Routes for Shaft Sites..... 11-6
11.3-1 Most Notable Significant or Temporary Adverse Construction Impacts, Potential Shaft Sites 11-7
11.3-2 Most Notable Significant or Temporary Adverse Construction Impacts, Water Main
Connection Routes 11-8
11.3-3 Socioeconomic Issues for Potential Shaft Sites..... 11-13
11.3-4 Number of Street Trees Potentially Affected Water Main Connection Routes for Shaft Sites 11-18
11.3-5 Water Main Connections to Preferred Shaft Site Summary of Temporary Adverse Traffic Impacts 11-22
11.3-6 Comparison of Noise Issues for Shaft Sites 11-24
11.3-7 Comparison of Temporary Adverse Noise Impacts for Water Main Connection Routes 11-26

CHAPTER 12: GROWTH-INDUCING IMPACTS..... 12-1

CHAPTER 13: IRRETRIEVABLE AND IRREVERSIBLE COMMITMENTS OF RESOURCES 13-1

CHAPTER 14: ENVIRONMENTAL SCREENING ANALYSES FOR ALL ALTERNATIVES

14.1 Introduction..... 14-1
14.2 Shadows..... 14-1
14.3 Natural Resources..... 14-2
14.4 Solid Waste and Sanitation 14-4

CHAPTER 15: COMMENTS AND RESPONSES

15.1 Introduction..... 15-1
15.2 List of Commenters 15-2
15.3 Comments and Responses..... 15-7

GLOSSARY AND ACRONYMSGlossary and Acronyms-1

APPENDICES

- Appendix 1 Site Screening**
- Appendix 2 Land Use and Community Facilities, Zoning, and Public Policy**
- Appendix 5 Historic Resources**
- Appendix 6 Visual Resources**

TABLE OF CONTENTS

- Appendix 9 Traffic and Parking**
- Appendix 10 Transit and Pedestrians**
- Appendix 11 Air Quality**
- Appendix 12 Noise**
- Appendix 14 Hazardous Materials**

