

Proposed Bike Corral:

Ideya Latin Bistro – 636 Carlton Ave



Spring
2014

Program Background

- DOT has installed 31 bike corrals city wide
- A bike corral is a row of bike racks installed in a curbside lane of a street
- Locations are identified based on requests from maintenance partners
- The maintenance partner is required to keep the site clear of debris and snow, maintain plantings, and report abandoned bicycles



5th Ave and Park Pl, Brooklyn
Installed: May 2012
Maintained by: Gorilla Coffee



82nd St & Roosevelt Ave, Queens
Installed: April 2013
Maintained by: 82nd St Partnership

Physical Guidelines

- Must be in a curbside lane that is never used as a travel lane
- May not block crosswalks, driveways, bus stops, and utility covers
- Must be a minimum of 15' away from fire hydrants or bus stops




8th Ave & W 21st St, Manhattan
Installed: April 2013
Maintained by: Organic Avenue



N 11 St & Wythe St, Brooklyn
Installed: September 2012
Maintained by: Kinfolk Studios

Project Background

- Requested by North Flatbush BID and Ideya
- Support from Prospect Heights Neighborhood Development Council



	Proposed Bike Corral		Protected Path
	Existing Bike Corral		Bike Lane
			Bike Route

Existing Conditions – Ideya

- Insufficient parking for neighborhood needs
- Bikes locked anywhere and everywhere



South on Carlton, outside Ideya



East across Flatbush Ave, looking towards Ideya

Proposed Improvements – Ideya

- Bike corral with space for 10 bicycles
- Remove 1 parking space on south side of Park Pl
 - Space is 2 hr muni meter parking
- Add 2 large planter pots
- Add 4 flexible delineators
- Add a lane line around corral



Questions?



**Thank
You**

Proposed Design - Ideya

Ideya
Bike Corral with Planters
636 Carlton Ave, Brooklyn
Draft Site Plan v 2013.7.5

5 single-mounted bicycle racks
 Spaced 34" on center, 27" from edge of plate
 34" from curb on center, 22" from curb on edge of plate
 Capacity for 10 bicycles
 2 Planters
 4 Flexible Delineators
 Flexible Delineators align 14'-6" from eastern curbline

Current Parking Regulations:
 No Parking 7:30AM-8:00AM
 Monday through Thursday



CITY OF NEW YORK		DEPARTMENT OF TRANSPORTATION	
DRAFT Bike Corral			
636 Carlton Ave, Brooklyn, NY			
APPROVED	Drawn by CDL	DRAWING	
BY	Checked by BK	Scale	NO.
	Date 2013.11.8		